

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In Re Reissue  
Application of: Bill L. Davis and Jesse S. Williamson

Entitled: COMBINED LITHOGRAPHIC/FLEXOGRAPHIC  
PRINTING APPARATUS AND PROCESS

For: Reissue of U.S. Patent 5,630,363

Filed: May 20, 1999

Serial No.: 09/315,796

Examiner: Not Yet Assigned

Group Art Unit: 2854

SUPPLEMENTAL STATEMENT OF PRIOR ART AND OTHER INFORMATION

APPENDIX 5

V. File History Pertinent to Series Commencing with  
UnitedStates Serial No. 08/435,798 filed May 4, 1995

Index No.      Description

65

File History of European Patent Application No. EP 0741 025 A3 entitled:  
Retractable Inking /Coating Apparatus having Ferris Movement between Printing  
Units, Applicant: Howard W. DeMoore; Inventors: Howard W. DeMoore, Ronald  
M. Rendleman and John W. Bird; Filed: May 5, 1993; Date of Publication A2:  
November 6, 1996

RECEIVED

AUG 05 1999

TECHNOLOGY CENTER 2800

RECEIVED

AUG 03 1999

TECHNOLOGY CENTER 2800

Figure 1 consists of 11 scatter plots, labeled (a) through (k), each showing the relationship between a specific variable and the number of children. The y-axis for all plots is 'Number of children'.

- (a) Age: Shows a positive correlation, with the number of children increasing as age increases.
- (b) Education: Shows a negative correlation, with the number of children decreasing as education level increases.
- (c) Income: Shows a positive correlation, with the number of children increasing as income increases.
- (d) Employment: Shows a positive correlation, with the number of children increasing as employment status improves.
- (e) Health: Shows a positive correlation, with the number of children increasing as health status improves.
- (f) Religion: Shows a positive correlation, with the number of children increasing as religion changes.
- (g) Ethnicity: Shows a positive correlation, with the number of children increasing as ethnicity changes.
- (h) Marital status: Shows a positive correlation, with the number of children increasing as marital status changes.
- (i) Family size: Shows a positive correlation, with the number of children increasing as family size increases.
- (j) Urban/rural: Shows a positive correlation, with the number of children increasing as the location changes from rural to urban.
- (k) Migration: Shows a positive correlation, with the number of children increasing as migration status changes.



EPA/EPO/OEB  
D-80298 München  
089/2399-0  
TX 523 656 epmu d  
FAX 089/2399-4465

Europäisches  
Patentamt

European  
Patent Office

Office européen  
des brevets

Generaldirektion 2

Directorate General 2

Direction Générale 2

BIRD & BIRD  
ATTN: MS. CECILIA CHEUNG  
90 FETTER LANE  
LONDON EC4A 1JP  
GREAT BRITAIN

## Rechnung / Invoice / Facture

Kundennummer  
Customer number 01500251  
Numéro du client

Datum/Date

20/07/99

Zeichen/Ref./Réf. <b>LIBRY.0666</b>	Anmeldung Nr./Application No./Demande n°/Patent Nr./Patent No./Brevet n°. <b>96303136.4 2304 0741025</b>
Anmelder/Applicant/Demandeur/Patentinhaber/Proprietor/Titulaire <b>DeMoore, Howard W.</b>	

### Übersendung von/Transmission of/Envoi de

Antrag vom/Request dated/Requête du 14/06/99

- ☒ Kopien bei Akteneinsicht nach Regel 94(3) EPÜ  
Copies in the case of inspection of files pursuant to Rule 94(3) EPC  
Copies en cas d'inspection publique selon la règle 94(3) CBE
- ☐ Beglaubigung  
Certification  
Certification
- ☐ ——— Prioritätsbeleg(e)/priority document(s)/document(s) de priorité R. 94(4)
- ☐ ——— Ausfertigung(en) der Patenturkunde nach Regel 54(2) EPÜ  
Duplicate of the patent certificate pursuant to Rule 54(2) EPC  
Duplicata du certificat de brevet, selon la Règle 54(2) CBE
- ☐ Auszug aus dem Register nach Regel 92(3) EPÜ  
Extract from the register pursuant to Rule 92(3) EPC  
Extrait du registre selon la Règle 92(3) CBE
- ☐ Auskunft aus den Akten nach Regel 95 EPÜ  
Communication of information contained in the files pursuant to Rule 95 EPC  
Communication d'informations contenues dans la dossier selon la Règle 95 CBE
- ☐ Akteneinsicht nach Regel 94(2) EPÜ  
Inspection of files pursuant to Rule 94(2) EPC  
Inspection publique selon la Règle 94(2) CBE

### Rechnung Nr./Invoice No./Facture N° 20189454

Bitte bei Zahlung unbedingt angeben  
Indicate number without fail when paying  
Ce n° doit absolument être indiqué lors du paiement

	EUR	Gegenwert Equivalent Contre-valeur GBP
Verwaltungsgebühr/Administration fee/Taxe d'administration	20,00	13,50
Kosten für Kopien/Cost of copies/Frais pour copies (145 Blätter) pages) feuilles)	87,00	58,00
Telefax	0,00	0,00
Summe/Total/Montant total	107,00	71,50
gezahlt sind/already paid/montant versé	0,00	0,00
noch zu zahlen/outstanding/reste à payer	107,00	71,50

☐ Der obengenannte Betrag wird abgebucht vom laufenden Konto  
The above sum will be debited from deposit account  
Le montant susmentionné sera débité du compte courant

Nr.  
No.  
n°

☒ Der obengenannte Betrag ist nach den auf der Anlage angegebenen Zahlungsmöglichkeiten zu entrichten (f. 2566.1 + 2).  
The above sum is payable as detailed on the annex (f. 2566.1 + 2).  
Le montant indiqué ci-dessus doit être acquitté suivant les modalités figurant sur l'annexe (f. 2566.1 + 2).

GARRY A G (TEL: 2375)



### Zahlungsmöglichkeiten

Nach Art. 5 der Gebührenordnung können die Gebühren wie folgt entrichtet werden:

- a) durch Einzahlung oder Überweisung auf ein Bankkonto des Amts,
- b) durch Einzahlung oder Überweisung auf ein Postscheckkonto des Amts,
- c) durch Übergabe oder Übersendung von Schecks, die an die Order des Amts lauten,
- d) durch Abbuchung von einem laufenden Konto beim Amt.

Die Zahlungswährung richtet sich nach der Währung des Staats, in dem das Konto geführt wird.

Der Betrag ist "ohne Kosten für den Empfänger" zu überweisen.

Das Verzeichnis der für die Europäische Patentorganisation eröffneten Bank- und Postscheckkonten, sowie der entsprechenden Zahlungswährungen ist auf Form 2566.2 abgedruckt.

### Methods of payment

Under Art. 5 of the rules relating to Fees the fees may be paid as follows:

- a) by payment or transfer to a bank account held by the Office,
- b) by payment or transfer to a giro account held by the Office,
- c) by delivery or remittance of cheques which are made payable to the Office,
- d) by debiting a deposit account held with the Office.

The currency for payment is determined by the currency of the State in which the account is held.

The fee is to be transferred "at no costs to the payee".

The list of bank and giro accounts opened in the name of the European Patent Organisation and corresponding currencies for payment is reproduced on Form 2566.2.

### Modalités de paiement

Aux termes de l'article 5 du Règlement relatif aux taxes, les taxes peuvent être acquittées comme suit:

- a) par versement ou virement à un compte bancaire de l'Office,
- b) par versement ou virement à un compte chèques postal de l'Office,
- c) par remise ou envoi de chèques établis à l'ordre de l'Office,
- d) par prélèvement sur un compte courant ouvert auprès de l'Office.

Le paiement doit être effectué dans la monnaie de l'Etat où le compte est ouvert.

Le virement doit se faire "sans frais pour le destinataire".

La liste des comptes bancaires et de chèques postaux ouverts au nom de l'Organisation européenne des brevets et des monnaies de paiement correspondantes est reprise sur le formulaire Form 2566.2.

Verzeichnis der für die  
Europäische Patentorganisation  
eröffneten Bank- und Post-  
scheckkonten sowie der  
entsprechenden  
Zahlungswährungen

List of bank and giro accounts  
opened in the name of the  
European Patent Organisation  
and corresponding currencies  
for payment

Liste des comptes bancaires et  
de chèques postaux ouverts au  
nom de l'Organisation  
européenne des brevets et  
des monnaies de paiement  
correspondantes

	Bankkonten Bank accounts Comptes bancaires	Postascheckkonten Giro accounts Comptes de chèques postaux	Zahlungswährung Currency for payment Monnaies de paiement
AT	N° 102-133-851/00 (BLZ 12000) Bank Austria AG Am Hof 2 A-1010 Wien	N° 7451 030 Österreichische Postsparkasse Georg-Coch-Platz 2 A-1018 Wien	Osterr. Schilling (ATS/EUR)
BE	N° 310-0449878-78 Banque Brucelles Lambert BP 948 B-1000 Bruxelles	N° 000-1154426-29 Banque de la Poste B-1100 Bruxelles	Franc belge (BEF/EUR)
CH	N° 322 005 01 B UBS CH-8021 Zurich	N° 30-30796-1 Zahlungsverkehr PTT Verarbeitungszentrum CH-4040 Basel	Franc suisse (CHF)
CY	N° 0155-06-000-650 Bank of Cyprus 21, Evagoras Av. P. O. Box 1472 CY - 1500 Nicosia		Cyprus Pound (CYP)
DE	N° 3 338 800 00 (BLZ 700 800 00) Dresdner Bank Promenadeplatz 7 D-80273 München	N° 300-800 (BLZ 700 100 80) Postbank München D-80318 München	Deutsche Mark (DEM/EUR)
DK	N° 3015133758 Den Danske Bank Holmens Kanal Dept. Holmens Kanal 2 DK-1090 København K.	N° 839-5893 GIROBANK A/S Girostrøget 1 DK-0800 Høje Taastrup	Danske kroner (DKK)
ES	N° 0104/0328/95/0303480024 Banco Exterior de España Carrera de San Jerónimo 36 E-28014 Madrid	N° 00-18716788 Caja Postal Cuentas Extranjeras Pº de Recoletas, 5 E-28070 Madrid	Peseta española (ESP/EUR)
FI	N° 200118-182076 Merita Bank Senastintori FIN-00020 Merita	N° 800013-90405 Leona Fabianinkatu 23 FIN-00007 Helsinki	Suomen Markka (FIM/EUR)
FR	N° 200 20463, Code banque 30 004, Code guichet 00 567, Cle Rib 28 Banque Nationale de Paris Agence France-Etranger 2 Place de l'Opéra F-75002 Paris		Franc français (FRF/EUR)
GB	N° 60 271 489 (sorting-code 20-00-00) Barclays Bank PLC 54 Lombard Street P. O. Box 544 GB-London EC3V 9EX		Pound Sterling (GBP)
GR	N° 112002002007046 Credit Bank AE Athens Tower Branch 2, Messoghion Avenue GR-115 27 Athens		Greek Drachma (GRD)
IE	N° 30982201 (Bank Code 90-14-90) Bank of Ireland Lower Baggot Street Branch P. O. Box 3131 IRL-Dublin 2		Irish pound (IEP/EUR)
IT	N° 935832 01 94, ABI 02002 / CAB 03200 Banca Commerciale Italiana Via del Plebiscito 112 I-00186 Roma	N° 10568277 Poste Italiane C. U. A. S. Piazza Vesuvio 6 I-20144 Milano	Lire italiana (ITL/EUR)
LU	N° 7-108/8134/200 Banque Internationale à Luxembourg 68, route d'Esch L-2953 Luxembourg	N° 26421-37 Administration des P & T Chèques postaux BP 2500 L-1000 Luxembourg	Franc belge (BEF/EUR)
MC	N° 254 22754, Code Banque 30 004, Code Guichet 09 179, Cle Rib 91 Banque Nationale de Paris Succursale de Monte-Carlo Galerie Charles III Avenue des Spélugues Boîte Postale 129 MC-95007 Monaco Cedex		Franc français (FRF/EUR)
NL	N° 51 36 39 547 ABN-AMRO Bank NV Kneuterdyk 1, Postbus 165 NL-2501 AP Den Haag	N° 4012627 Postbank NV NL-6800 MA Arnhem	Nederlandsse Gulden (NLG/EUR)
PT	N° 0015/020 0808391145 / 05 Banco Pinto et Sotto Mayor Av. Fontes Pereira de Melo 7 P-1000 Lisboa		Escudo português (PTE/EUR)
SE	N° 122 687 108 Bankgiro N° 5843-6155 Svenska Handelsbanken S-10670 Stockholm	N° 7 41 53-8 Postgirot S-10506 Stockholm	Svenska kronor (SEK)

Vollmacht / Authorisation / Pouvoir:

ist beigefügt / is enclosed / ci-joint

ist registriert unter Nummer / has been registered  
under No. / a été enregistré sous le n°

GENA

ERFINDER / INVENTOR / INVENTEUR:

INVT 20 # #

Anmelder ist (sind) alleinige(r) Erfinder / The applicant(s) is (are)  
the sole inventor(s) / Le(s) demandeur(s) est (sont) le (les) seul(s)  
inventeur(s)

Erfindernennung auf gesondertem Schriftstück / Designation of  
inventor attached / Voir la désignation de l'inventeur ci-jointe

BEZEICHNUNG DER ERFINDUNG / TITLE OF INVENTION /  
TITRE DE L'INVENTION:

TIDE

TIEN

TIFR

PRIORITÄTSEKRLARUNG / DECLARATION OF PRIORITY /  
DECLARATION DE PRIORITE

PRIO

01 # # #

02 # # #

03 # # #

04 # # #

Weitere Prioritätserklärungen auf Zusatzblatt /  
Additional declaration(s) of priority on additional sheet /  
Autre(s) déclaration(s) de priorité sur feuille additionnelle

#### MIKROORGANISMEN

Die Erfindung betrifft einen Mikro-  
organismus (mehrere Mikroorganis-  
men) oder seine (ihre) Verwendung,  
der (die) auf Grund des Budapest-  
Vertrages oder eines bilateralen  
Abkommens zwischen der Hinter-  
legungsstelle und dem EPA nach  
Regel 28(1) a) bei einer anerkannten  
Hinterlegungsstelle hinterlegt worden  
ist (sind), um die Bedingungen für die  
Offenbarung der Erfindung gemäß  
Artikel 83 in Verbindung mit  
Regel 28 zu erfüllen

#### MICRO-ORGANISMS

The invention relates to and/or uses  
(a) micro-organism(s) deposited for  
the purposes of disclosure pursuant  
to Article 83 in conjunction with  
Rule 28 with a depositary institution  
recognised within the meaning of  
Rule 28(1) (a) under either the  
Budapest Treaty or a bilateral  
agreement between the institution  
and the EPO

MICO 1 # # # # # # # #

Die Angaben nach Regel 28(1) c) sind in den technischen Anmeldungs-  
unterlagen enthalten auf / The particulars referred to in Rule 28(1) (c) are  
given in the technical documents in the application on / Les indications  
visées à la règle 28(1) c) figurent dans les pièces techniques de la  
demande à la /aux

werden später mitgeteilt / will be submitted at a later date /  
seront communiquées ultérieurement

Die Empfangsbescheinigung(en) der Hinterlegungsstelle ist (sind)  
beigefügt / The receipt(s) of deposit issued by the depositary institution  
is (are) enclosed / Le(s) récépissé(s) de dépôt délivré(s) par l'autorité  
de dépôt est (sont) ci-joint(s)

wird (werden) nachgereicht / will be filed at a later date /  
sera (seront) produit(s) ultérieurement

20

21

22

23

24

RETRACTABLE INKING/COATING APPARATUS  
HAVING FERRIS MOVEMENT BETWEEN  
PRINTING UNITS

25

Staat / State / Etat

Anmeldetag / Filing  
date / Date de dépôt

Anzeichen / Application  
No. / N° de la demande

1 US 4 May 1995 08/435,798

2

3

4

26

#### MICRO-ORGANISMES

L'invention concerne un (plusieurs)  
micro-organisme(s) et/ou utilise un  
(plusieurs) micro-organisme(s),  
déposé(s) afin de satisfaire aux  
conditions d'expose de l'invention  
prévues à l'article 83 ensemble  
la règle 28, à cet effet, le dépôt a été  
effectué auprès d'une autorité  
habilitée au sens de la règle 28(1) a),  
en vertu soit du Traité de Budapest,  
soit d'un accord bilatéral entre  
l'autorité et l'OEB

27

Seite(n) / page(s)

Zeile(n) / line(s) / ligne(s)

28

29

30

NUCLEOTID-UND AMINOSÄURESEQUENZEN / NUCLEOTIDE  
AND AMINO ACID SEQUENCES / SEQUENCES DE  
NUCLEOTIDES ET D'ACIDES AMINES

SEQL (1) 31

Die Beschreibung enthält ein Sequenzprotokoll nach Regel 27a(1) / The description contains a sequence listing in accordance with Rule 27a(1) / La description contient une liste de séquences selon la règle 27bis(1)

Der vorgeschriebene maschinenlesbare Datenträger ist beigelegt / The prescribed machine readable data carrier is enclosed / Le support de données prescrit déchiffable par machine est annexé

Es wird hiermit erklärt, daß die auf dem Datenträger gespeicherte Information mit dem schriftlichen Sequenzprotokoll übereinstimmt (Regel 27a(2)) / It is hereby stated that the information recorded on the data carrier is identical to the written sequence listing (Rule 27a(2)) / Il est déclaré par la présente que l'information figurant sur le support de données est identique à celle que contient la liste de séquences écrite (règle 27bis (2))

Verschiedene Anmelder für verschiedene Vertragsstaaten / Different applicants for different Contracting States / Différents demandeurs pour différents Etats contractants

32 Name(n) des (der) Anmelder(s) und benannte Vertragsstaaten / Name(s) of applicant(s) and designated Contracting States / Nom(s) du (des) demandeur(s) et des Etats contractants désignés

APPR 02 #

BENENNUNG VON VERTRAGSSTAATEN  
DESIGNATION OF CONTRACTING STATES  
DESIGNATION D'ETATS CONTRACTANTS

DEST 33

Osterreich / Austria / Autriche

AT

Belgien / Belgium / Belgique

BE

Schweiz und Liechtenstein / Switzerland and  
Liechtenstein / Suisse et Liechtenstein

CH / LI

Deutschland / Germany / Allemagne

DE

X

Danemark / Denmark / Danemark

DK

Spanien / Spain / Espagne

ES

Frankreich / France / France

FR

X

Vereinigtes Königreich / United Kingdom / Royaume-Uni

GB

X

Griechenland / Greece / Grece

GR

Irland / Ireland / Irlande

IE

Italien / Italy / Italie

IT

X

Luxemburg / Luxembourg / Luxembourg

LU

Monaco / Monaco / Monaco

MC

Niederlande / Netherlands / Pays-Bas

NL

Portugal / Portugal / Portugal

PT

Schweden / Sweden / Suede

SE

X

(Platz für Vertragsstaaten, für die das EPU nach  
Drucklegung dieses Formblatts in Kraft tritt)

(Space for Contracting States for which the EPC  
enters into force after this form has been printed)

VORSÖRGLICHE BENENNUNG  
SAMTLICHER VERTRAGSSTAATEN

Die in Feld 33 angegebenen Staaten sind jene, für die die Zahlung der Benennungsgebühren vorgenommen wurde oder derzeit beabsichtigt ist. Vorsorglich werden jedoch sämtliche Staaten benannt, die zum Zeitpunkt der Einreichung dieser Anmeldung Vertragsstaaten des EPU sind (1.10.1995 AT, BE, CH, DE, DK, ES, FR, GB, GR, IE, IT, LI, LU, MC, NL, PT, SE). Es wird ersucht, die Benennung der hier zusätzlich benannten Vertragsstaaten als vom Anmelder zurückgenommen zu betrachten, wenn für diese Staaten die Benennungsgebühren nicht bis zum Ablauf der in Regel 85a(2) vorgesehenen Nachfrist entrichtet werden. Es wird beantrag, von der Zustellung einer Mitteilung nach Regel 85a(1) und einer Mitteilung nach Regel 69(1) betreffend die hier zusätzlich benannten Vertragsstaaten abzusehen.

PRECAUTIONARY DESIGNATION OF  
ALL CONTRACTING STATES

The States indicated in Section 33 are those for which it is at present intended to pay designation fees if these have not already been paid. As a precautionary measure, however, all those States which are Contracting States to the EPC at the time of filing this application are designated (1.10.1995 AT, BE, CH, DE, DK, ES, FR, GB, GR, IE, IT, LI, LU, MC, NL, PT, SE). It is hereby requested that the designation of any additional States thereby included be regarded as withdrawn by the applicant if the designation fees have not been paid by the time the period of grace allowed in Rule 85a(2) expires. It is requested that no communication under Rule 85a(1) nor any communication under Rule 69(1) concerning the additional Contracting States designated above be notified.

33a



DESIGNATION A TOUTES FINS UTILES  
DE TOUS LES ETATS CONTRACTANTS

Les Etats indiqués à la rubrique 33 sont ceux pour lesquels le paiement des taxes de désignation a été effectué ou pour lesquels l'on se propose actuellement de payer les taxes de désignation. Toutefois, à toutes fins utiles, sont désignés tous les Etats qui sont des Etats contractants de la CBE à la date du dépôt de la demande (1.10.1995 AT, BE, CH, DE, DK, ES, FR, GB, GR, IE, IT, LI, LU, MC, NL, PT, SE). Il est demandé, au cas où les taxes de désignation pour les Etats contractants désignés à titre complémentaire ne seraient pas acquittées dans le délai supplémentaire prévu à la règle 85bis(2), que la désignation desdits Etats soit considérée comme retirée par le demandeur. Prière de ne pas procéder pour lesdits Etats contractants désignés à titre complémentaire à la signification d'une notification établie conformément à la règle 85bis(1) ou à la règle 69(1).

# ERSTRECKUNG DES EUROPAISCHEN PATENTS

Diese Anmeldung gilt als Antrag, die europäische Patentanmeldung und das darauf erteilte europäische Patent auf alle Nicht-Vertragsstaaten des EPU zu erstrecken, mit denen am Tag ihrer Einreichung „Erstreckungsabkommen“ bestehen (Derzeit: Litauen, Lettland, Slowenien).  
Die Erstreckung wird jedoch nur wirksam, wenn die vorgeschriebene Erstreckungsgebühr entrichtet wird.

# EXTENSION OF THE EUROPEAN PATENT

This application is deemed to be a request to extend the European patent application and the European patent granted in respect of it to all non-Contracting States to the EPC with which "extension agreements" exist on the date on which the application is filed (Present situation: Lithuania, Latvia, Slovenia).  
However, the extension only takes effect if the prescribed extension fee is paid.

34

# EXTENSION DES EFFETS DU BREVET EUROPEEN

La présente demande est réputée constituer une requête en extension des effets de la demande de brevet européen et du brevet européen délivré sur la base de cette demande à tous les États non parties à la CBE avec lesquels il existe un «accord d'extension» à la date du dépôt de la demande (Situation actuelle: Lituanie, Lettonie, Slovaquie).  
Toutefois l'extension ne produit ses effets que s'il est acquitté la taxe d'extension prescrite.

EXPT

Der Anmelder beabsichtigt derzeit, die Erstreckungsgebühr für die nachfolgend angekreuzten Staaten zu entrichten: /  
The applicant currently intends to pay the extension fee for the States marked below with a cross. /  
Le demandeur se propose actuellement d'acquitter la taxe d'extension pour les États dont le nom est coché ci-après:

Litauen / Lithuania / Lituanie

LT

Lettland / Latvia / Lettonie

LV

Slowenien / Slovenia / Slovaquie

SI

Platz für Signaturen und nach Drucklegung dieses Formblatts, Erstreckungskommission, in Kraft tretend /  
Space for Signatures and, after completion of this form, extension commission, in force /  
Espace pour les signatures et, après l'achèvement de ce formulaire, extension commission, en vigueur

Die Anmeldung ist eine Teilanmeldung /  
The application is a divisional application /  
La présente demande constitue une demande divisionnaire

DFIL 9

#

PANR

#

35

Nummer der früheren Anmeldung  
No. of earlier application  
Numero de la demande initiale

Es handelt sich um eine Anmeldung nach Art. 61(1)(b) /  
The application is an Art. 61(1)(b) application /  
La présente demande constitue une demande selon l'article 61(1)(b)

DFIL 9

#

EANR

#

36

Nummer der früheren Anmeldung  
No. of earlier application  
Numero de la demande initiale

Patentansprüche / Claims / Revendications

CLMS

37

22

Zahl der Patentansprüche  
Number of claims  
Nombre de revendications

Weiterer Satz von Patentansprüchen (Art. 167(2)(a)) /  
Additional set of claims (Art. 167(2)(a)) /  
Série supplémentaire de revendications (art. 167(2)(a))

AUCL (1)

AUCL (3)

AUCL (4)

38

AT  
ES  
GR

Zahl der Patentansprüche  
Number of claims  
Nombre de revendications

Zur Veröffentlichung mit der Zusammenfassung wird vorgeschlagen  
Abbildung Nr. / With the abstract it is proposed to publish  
figure No. / Il est proposé de publier avec l'abrégé  
la figure n°

DRAW (2)

39

1

Nummer / Number / Numero

Zusätzliche Abschrift(en) der im europäischen Recherchenbericht angeführten Schriftstücke wird (werden) beantragt / Additional copy(ies) of the documents cited in the European search report is (are) requested /  
Prière de fournir une (des) copie(s) supplémentaire(s) des documents cités dans le rapport de recherche européenne

ASOC

40

1

Anzahl der **zusätzlichen** Sätze von Abschriften  
Number of **additional** sets of copies  
Nombre de jeux **supplémentaires** de copies



Es wird die Rückerstattung der Recherchegebühr gemäß Art. 10 GebO beantragt / Refund of the search fee is requested pursuant to Article 10 of the Rules relating to Fees / Le remboursement de la taxe de recherche est demandé en vertu de l'article 10 du règlement relatif aux taxes

41 ☐

Eine Kopie des Recherchenberichts ist beigelegt / A copy of the search report is attached / Une copie du rapport de recherche est jointe

42 ☐

**AUTOMATISCHER ABBUCHUNGSAUFTRAG** (nur möglich für Inhaber von einem EPO- oder EPO-ähnlichen Konto)  
**AUTOMATIC DEBIT ORDER** (for EPO deposit account holders only)  
**ORDRE DE PRELEVEMENT AUTOMATIQUE** (uniquement possible pour les titulaires de comptes courants ouverts auprès de l'OEB)

Das Europäische Patentamt wird hiermit beauftragt, fällig werdende Gebühren und Auslagen nach Maßgabe der Vorschriften über das automatische Abbuchungsverfahren vom nebenstehenden laufenden Konto abzubuchen / The European Patent Office is hereby authorised, under the Arrangements for the automatic debiting procedure, to debit from the deposit account opposite any fees and costs falling due / Par la présente, il est demandé à l'Office européen des brevets de prélever du compte courant ci-contre les taxes et frais venant à échéance, conformément à la réglementation relative au prélèvement automatique

DECA

Nummer des laufenden Kontos / Name des Kontoinhabers /  
 Deposit account number / Account holder's name /  
 Numéro du compte courant / Nom du titulaire du compte

43

Eventuelle Rückzahlungen auf das nebenstehende beim EPA geführte laufende Konto / Reimbursement, if any, to EPO deposit account opposite / Remboursements éventuels à effectuer sur le compte courant ci-contre ouvert auprès de l'OEB

DEPA

Nummer des laufenden Kontos / Name des Kontoinhabers /  
 Deposit account number / Account holder's name /  
 Numéro du compte courant / Nom du titulaire du compte

44

2805.0013

Die vorgeschriebene Liste über die diesem Antrag beigelegten Unterlagen ergibt sich aus der vorbereiteten Empfangsbescheinigung (Seite 6 dieses Antrages)

The prescribed list of documents enclosed with this request is shown on the prepared receipt (page 6 of this request)

45

La liste prescrite des documents joints à cette requête figure sur le récépissé préétabli (page 6 de la présente requête)

Unterschrift(en) des (der) Anmelders(s) oder Vertreter(s) /  
 Signature(s) of applicant(s) or representative(s) /  
 Signature(s) du (des) demandeur(s) ou du (des) mandataire(s)

46

Für Angestellte nach Artikel 133 (3) Satz 1 mit allgemeiner Vollmacht / For employees under Article 133 (3), 1st sentence, having a general authorisation / Pour les employés mentionnés à l'article 133, paragraphe 3, 1re phrase, munis d'un pouvoir général Nr. / No. / n°:

Ort / Place / Lieu London, GB

Datum / Date 3 May 1996



H. A. GURA  
 AUTHORISED REPRESENTATIVE

In this application, unless expressly stated otherwise, the cancellation, abandonment or amendment of any claim or any amendment in the description does not amount to abandonment of any subject matter in the application and upon any such cancellation, abandonment or amendment the right to file divisional applications in respect of any subject matter in the application as filed is maintained.

Name des oder der Unterzeichnenden mit Schreibmaschinenschrift: Bei juristischen Personen bitte die Stellung des (der) Unterzeichneten innerhalb der Gesellschaft mit Schreiben zu geben / Please type name under signature: In case of legal persons, the position of the signatory within the company should also be typed / Le ou les noms et la position de la ou des signataires doivent être indiqués: Si s'agit d'une personne morale, la position occupée au sein de celle-ci par le ou les signataires sera indiquée à la même adresse

# Empfangsbescheinigung / Receipt for document / Récépissé de documents

(Liste der diesem Antrag beigefügten Unterlagen)

(Checklist of enclosed documents)

(Liste des documents annexes à la présente requête)

Es wird hiermit der Empfang der unten bezeichneten Dokumente bescheinigt / Receipt of the documents indicated below is hereby acknowledged / Nous attestons le dépôt des documents désignés ci-dessous

Wird im Falle der Einreichung der europäischen Patentanmeldung bei einer nationalen Behörde diese Empfangsbescheinigung vom Europäischen Patentamt übersandt, so ist sie als Mitteilung gemäß Regel 24(4) anzusehen (siehe Feld RENA). **Nach Erhalt der Mitteilung nach Regel 24(4) sind alle weiteren Unterlagen, die die Anmeldung betreffen, nur noch unmittelbar beim EPA einzureichen.** / If this receipt is issued by the European Patent Office and the European patent application was filed with a national authority it serves as a communication under Rule 24(4) (see Section RENA). **Once the communication under Rule 24(4) has been received, all further documents relating to the application must be sent directly to the European Patent Office.** / Si, en cas de dépôt de la demande de brevet européen auprès d'un service national, l'Office européen des brevets délivre le présent récépissé de documents, ce récépissé est réputé être la notification visée à la règle 24(4). **Des que la notification visée à la règle 24(4) a été reçue, tous les autres documents relatifs à la demande doivent être adressés directement à l'OEB.**

MEWBURN ELLIS  
York House  
23 Kingsway  
LONDON WC2B 6HP

Applicant: Howard W DEMOORE

Nur für amtlichen Gebrauch / For official use only / Cadre réservé à l'administration

Datum / Date

Unterschrift / Amtssiegel / Signature / Official stamp / Signature / Cachet officiel

Anmeldenummer / Application No. / N° de la demande

Tag des Eingangs (Regel 24(2)) / Date of receipt (Rule 24(2)) / Date de réception (règle 24(2))

DREC

Zeichen des Anmelders/Vertreters / Applicant's/ Representative's / Référence du demandeur ou du mandataire

AREF

Nur nach Einreichung der Anmeldung bei einer nationalen Behörde / Only after filing of the application with a national authority / Seulement après le dépôt de la demande auprès d'un service national

Tag des Eingangs beim EPA (Regel 24(4)) / Date of receipt at EPO (Rule 24(4)) / Date de réception à l'OEB (règle 24(4))

RENA

14.05.96

A. Anmeldungsunterlagen und Prioritätsbelege / Application documents and priority document(s) / Pièces de la demande et document(s) de priorité

47

1. Beschreibung / Description

2. Patentansprüche / Claim(s) / Revendication(s)

3. Ggf. unterschiedliche Patentansprüche (Art. 167(2) a) / Any different claims (Art. 167(2)(a)) / Le cas échéant, revendications différentes (art. 167(2) a))

4. Zeichnungen / Drawing(s) / Dessin(s)

DRAW 1 #

5. Zusammenfassung / Abstract / Abrégé

6. Übersetzung der Anmeldungsunterlagen / Translation of the application documents / Traduction des pièces de la demande

7. Prioritätsbeleg(e) / Priority document(s) / Document(s) de priorité

B. Der Anmeldung in der eingereichten Fassung liegen folgende Unterlagen bei: / This application as filed is accompanied by the items below: / A la présente demande sont annexées les pièces suivantes:

48

1. Einzelvollmacht / Specific authorisation / Pouvoir particulier

2. Allgemeine Vollmacht / General authorisation / Pouvoir général

3. Erfindernennung / Designation of inventor / Désignation de l'inventeur

4. Früherer Recherchenbericht / Earlier search report / Rapport de recherche antérieure

5. Gebührenzahlungsvordruck (EPA Form 1010) / Voucher for the settlement of fees (EPO Form 1010) / Bordereau de règlement de taxes (OEB Form 1010)

6. Scheck (ausgeschlossen bei Einreichung bei den nationalen Behörden) / Cheque (not when filing with national authorities) / Chèque (pas de chèque en cas de dépôt auprès des services nationaux)

7. Datenträger für Sequenzprotokoll / Data carrier for sequence listing / Support de données pour liste de séquences

SEQ (4)

8. Zusatzblatt / Additional sheet / Feuille additionnelle

9. Sonstige Unterlagen (bitte hier spezifizieren) / Other (please specify here) / Autres documents (veuillez préciser ici)

C. Kopien dieser Empfangsbescheinigung / Copies of this receipt for documents / Copies du présent récépissé de documents

49

3

Währungsbetrag / Currency Amount / Montant monétaire (Ausfüllung freigestellt / optional / facultatif)

\* Die Richtigkeit der Angabe der Blattzahl wurde beim Eingang nicht geprüft / No check was made on receipt that the number of sheets indicated was correct / L'exactitude du nombre de feuilles n'a pas été vérifiée

EPA/EPO/OEB Form 1001 6 10 95

HAG/FP5233994

Abgegeben am: / Filed on: / Déposé le: / Date of filing

6

2.

[illegible]

WALTON, SEÁN M.

all at MEWBURN ELLIS, York House, 23 Kingsway, London, WC2B 6HP, GB

# ERFINDERNENNUNG / DESIGNATION OF INVENTOR / DESIGNATION DE L'INVENTEUR

(falls Anmelder nicht oder nicht allein der Erfinder ist) : (where the applicant is not the inventor or is not the sole inventor) / (si le demandeur n'est pas l'inventeur ou l'unique inventeur)

Zeichen des Anmelders oder Vertreters  
Applicant's or representative's reference  
Reference du demandeur ou du mandataire  
(max 15 Positionen / max 15 spaces /  
15 caractères au maximum)

HAG/FP5233994

Nr. der Anmeldung oder, falls noch nicht bekannt, Bezeichnung der Erfindung  
Application N° or, if not yet known, title of the invention  
N° de la demande ou, si ce dernier n'est pas encore connu, titre de l'invention

RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS

In Sachen der obenbezeichneten europäischen Patentanmeldung nennt (nennen) der (die) Unterzeichnete(n)<sup>1</sup>  
In respect of the above European patent application I (we), the undersigned<sup>1</sup>  
En ce qui concerne la demande de brevet européen susmentionnée le (s) soussigné(s)<sup>1</sup>

Howard W DEMOORE  
10954 Shady Trail  
Dallas  
Texas 75220  
USA

als Erfinder<sup>2</sup>:  
do hereby designate as inventor(s)<sup>2</sup>:  
désigne(nt) en tant qu'inventeur(s)<sup>2</sup>:

Howard W DEMOORE, 10954 Shady Trail, Dallas, Texas 75220, USA  
Ronald M RENDLEMAN, 4331 Royal Ridge, Dallas, Texas 75229, USA  
John W BIRD, 1514 Iroquois Circle, Carrollton, Texas 75007, USA

☐ (Weitere Erfinder sind auf einem gesonderten Blatt angegeben) / (Additional inventors indicated on supplementary sheet)  
(les autres inventeurs sont mentionnés sur une feuille supplémentaire).

Der (Die) Anmelder hat (haben) das Recht auf das europäische Patent erlangt<sup>3</sup>  
The applicant(s) has (have) acquired the right to the European patent<sup>3</sup>  
Le(s) demandeur(s) a (ont) acquis le droit au brevet européen<sup>3</sup>

☒ gemäß Vertrag vom 1 May 1995  
under an agreement dated 1 May 1995  
par contrat en date du 1 May 1995

☐ als Arbeitgeber  
as employer(s)  
en qualité d'employeur(s)

☐ durch Erbfolge  
as successor(s) in title  
par transfert successoral

Ort/Place/Lieu London, GB

Datum/Date 3 May 1996

Unterschrift(en) des (der) Anmelder(s) oder Vertreter(s) /  
Signature(s) of applicant(s) or representative(s) /  
Signature(s) du (des) demandeur(s) ou du (des) mandataire(s)

H A GURA  
AUTHORISED REPRESENTATIVE

Name des (der) Unterzeichneten bitte mit Schreibmaschine wiederholen. Bei juristischen Personen bitte die Stellung des (der) Unterzeichneten innerhalb der Gesellschaft mit Schreibmaschine angeben / Please type name under signature in case of legal persons, the position of the signer within the company should also be typed. Le ou les noms des signataires doivent être également dactylographiés. S'il s'agit d'une personne morale, la position occupée au sein de celle-ci par le ou les signataires sera indiquée à la machine à écrire

Fußnoten befinden sich auf der Rückseite / Footnotes overleaf / Le texte des renvois figure au verso

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS"

This invention relates to sheet-fed or web-fed, rotary offset or flexographic printing presses, and more particularly, to a new and improved inking/coating apparatus for the in-line application of printing inks or protective or decorative coatings to sheet or web substrates.

Conventional sheet-fed, rotary offset printing presses typically include one or more printing units through which individual sheets are fed and printed with wet ink. Since the inks used with rotary offset printing presses typically remain wet and tacky for some time after printing, special precautions must be taken to insure that the freshly printed sheets are not marked or smeared as the sheets are transferred from one printing unit to another, and while being conveyed to the sheet delivery stacker. The printed surface of the freshly printed sheet dries relatively slowly and can be smeared during subsequent transfer between printing units. In order to reduce smearing and offsetting, spray powder is applied on the printed sheet.

In some printing applications, offset and smearing are prevented by applying a protective and/or decorative coating over all or a portion of the freshly printed sheets. Various arrangements have been proposed for applying the protective or decorative coating as an in-line operation by using the last printing unit of the press as the coating application unit. However, when such in-

0945796-051101  
TOP SECRET

line coating is performed, the last printing unit cannot be used to apply ink to the sheets, and can only be used for the coating operation. Thus, while coating with these types of in-line coating apparatus, the press loses the capability of printing its full range of colors since the last printing unit is converted to a coating unit.

It will be appreciated that the time required to reconfigure a press for coating or non-coating is non-productive and costly. Accordingly, there is a need for an in-line coating apparatus that minimizes the time to clean-up from one printing run and set-up and run the next job. Where consecutive jobs require the same type of coating, particularly blanket coating, it may not be necessary to clean-up the coater between jobs. However, the coating material cannot be allowed to dry on the rollers. Therefore, especially when switching from blanket to spot coating or vice versa, or if there is a delay between jobs, it is necessary to wash-up the coater after each job is completed.

In addition, coater wash-up is necessary when switching between different coating compositions, such as aqueous and ultra violet (UV) curable coatings. Such coating materials are not interchangeable, and consequently, the coater must be washed between applications of different coating media.

The foregoing limitations are overcome, according to the present invention, by a retractable, in-line inking/coating apparatus which is mounted on a printing

09316796 051107  
TOP SECRET

unit for pivotal, Ferris wheel movement between an operative inking/coating position and a retracted, overhead idle position. The inking/coating apparatus includes an applicator head which, is positioned in alignment with  
5 either the plate cylinder or the blanket cylinder by a carriage assembly which includes a cantilevered support arm. The support arm is pivotally coupled between the inking/coating head and the printing unit tower. This cantilevered, pivotal mounting arrangement allows the ink-  
10 ing/coating unit to be used between two printing units, as well as on the last printing unit of the press.

In the preferred embodiment, the applicator head includes vertically spaced pairs of cradle members with one cradle pair being adapted for supporting a metal or ceramic  
15 coating roller in alignment with a blanket cylinder, and the other cradle pair supporting a resilient anilox coating roller in alignment with the plate cylinder, respectively, when the carriage assembly is in the operative position. Because of the cantilevered, pivotal support provided by  
20 the support arm, the applicator head can be lifted and lowered through an arc, similar to Ferris wheel movement, in the limited space between adjacent printing units. When fully retracted, the applicator head and carriage assembly are lifted to an elevated, retracted overhead position,  
25 preferably an overhead position overlying the printing unit tower, thus providing complete access to the interstation space and the printing unit cylinders without causing the printing unit to lose its printing capability. The

0345796 154104

inking/coating applicator roller of the applicator head can be inspected, cleaned or replaced and the doctor blade assembly can be washed-up automatically while the ink-inking/coating apparatus is in the retracted position.

5                   When the inking/coating apparatus is used in combination with a flexographic printing plate and aqueous ink or aqueous coating, the water component of the aqueous ink or coating on the freshly printed sheet is evaporated by a high velocity, hot air interstation dryer and a high  
10 volume heat and moisture extractor assembly so that the freshly printed ink or coating is completely dry before the sheet is printed on the next printing unit. This quick drying flexographic printing/coating arrangement permits a base coat of ink, for example opaque white or metallic ink  
15 (gold, silver or other metallics) to be applied in the first printing unit, and then overprinted by a lithographic process on the next printing unit.

Exemplary embodiments of the present invention are illustrated in the drawing figures wherein:

20                   FIGURE 1 is a schematic side elevational view of a sheet-fed, rotary offset printing press having ink-inking/coating apparatus embodying the present invention;

                  FIGURE 2 is a perspective view of the printing press of FIGURE 1 in which a dual head inking/coating  
25 apparatus is in the operative coating position and a single head coater is in a retracted, overhead position;

0935796-01401



FIGURE 3 is an enlarged simplified perspective view showing one side of the single head inking/coating apparatus of FIGURE 1 in the operative position;

FIGURE 4 is a simplified side elevational view showing the dual head inking/coating apparatus in the operative coating position for spot or overall coating from the blanket position;

FIGURE 5 is a simplified side elevational view showing the single head inking/coating apparatus in the operative coating position for spot or overall coating from the plate position; and,

FIGURE 6 is a simplified side elevational view of the dual head inking/coating apparatus of FIGURE 4, partially broken away, which illustrates the hydraulic drive assembly and doctor blade assembly.

As used herein, the term "processed" refers to various printing methods which may be applied to either side of a substrate, including the application of UV-curable and aqueous inks and/or coatings. The term "substrate" refers to sheet or web material. Also, as used herein, the term "waterless printing plate" refers to a printing plate having non-image surface areas which are hydrophobic and also having image surface areas which are hydrophilic, wherein the non-image surface areas are characterized by a surface tension value which is less than the surface tension of aqueous ink, and the image surface areas are characterized by a surface tension value which is greater than the surface tension of aqueous ink. "Flexo-

graphic" refers to flexible printing plates having a relief surface which is wettable by aqueous ink or aqueous coating material.

As shown in the exemplary drawings, the present invention is embodied in a new and improved in-line inking/coating apparatus 10, for applying inks or protective and/or decorative coatings to sheets or webs printed in a sheet-fed or web-fed, rotary offset or flexographic printing press, herein generally designated 12. In this instance, as shown in FIGURE 1, the inking/coating apparatus 10 is installed in a four color printing press 12, such as that manufactured by Heidelberger Druckmaschinen AG of the Federal Republic of Germany under its designation Heidelberg Speedmaster 102V. The press 12 includes a press frame 14 coupled at one end, herein the right end, to a sheet feeder 16 from which sheets, herein designated S, are individually and serially fed into the press, and at the opposite end, with a sheet delivery stacker 20 in which the freshly printed sheets are collected and stacked. Interposed between the sheet feeder 16 and the sheet delivery stacker 20 are four substantially identical rotary offset printing units 22, 24, 26 and 28 which can print different color inks onto the sheets as they are transferred through the press 12. The printing units are housed within printing towers T1, T2, T3 and T4 formed by side frame members 14, 15.

As illustrated, the printing units 22, 24, 26 and 28 are substantially identical and of conventional design.

The first printing unit 22 includes an in-feed transfer cylinder 30, a plate cylinder 32, a blanker cylinder 34 and an impression cylinder 36, all supported for rotation in parallel alignment between the press side frames 14, 15.

5 Each of the first three printing units 22, 24 and 26 have an interunit transfer cylinder 38 disposed to transfer the freshly printed sheets from the adjacent impression cylinder to the next printing unit via an interstation transfer cylinder 40. The last printing unit 28 is shown  
10 equipped with a delivery cylinder 42 which guides each freshly printed sheet 18 as it is transferred from the last impression cylinder 36 to a delivery conveyor system, generally designated 44, to the sheet delivery stacker 20.

The delivery conveyor system 44 as shown in  
15 FIGURE 2 is of conventional design and includes a pair of continuous delivery gripper chains 46, only one of which is shown carrying at regular spaced locations along the chains, laterally disposed gripper bars having gripper fingers for gripping the leading edge of a freshly printed  
20 sheet 18 after it leaves the nip between the delivery cylinder 42 and impression cylinder 36 of the last printing unit 28. As the leading edge is gripped by the grippers, the delivery chains 46 pull the freshly printed sheet away from the impression cylinder 36 and deliver the freshly  
25 printed sheet to the sheet delivery stacker 20.

Prior to reaching the delivery sheet stacker, the freshly printed and/or coated sheets S pass under a delivery dryer 48 which includes a combination of infra-red

00345796 554404

thermal radiation, high velocity hot air flow and heat and moisture extraction for drying the ink and/or the protective/decorative coating on the freshly printed sheets.

In the exemplary embodiment shown in FIGURE 1, the first printing unit 22 is equipped with a flexographic printing plate, and does not require an inking roller train or a dampening system. If an ink roller train is mounted on the first printing unit, the form rollers are retracted and locked off when the printing unit goes on impression. Flexographic aqueous ink is supplied by the inking/coating unit 110. The remaining printing units 24, 26 and 28 are equipped for lithographic printing and include an inking apparatus 50 having an inking roller train 52 arranged to transfer ink from an ink fountain 54 to the plate cylinder 32. This is accomplished with the aid of a fountain roller 56 and a ductor roller. The fountain roller 56 projects into the ink fountain 54, whereupon its surface is wetted with printing ink Q. The printing ink Q is transferred intermittently to the inking roller train 52 by the ductor roller. The inking roller train 52 supplies printing ink Q to the image areas of a printing plate P mounted on the plate cylinder 32.

The printing ink Q is transferred from the printing plate P to an ink receptive blanket B which is mounted on the blanket cylinder 34. The inked image carried on the blanket B is transferred to a sheet S as the sheet is transferred through the nip between the impression cylinder 36 and the blanket B.

03315796-054101

The inking roller arrangement 52 illustrated in FIGURE 1 is exemplary for use in combination with lithographic ink printing plates. It will be understood that dampening rollers (not illustrated) will be in direct engagement with the lithographic plate P, but are not used in combination with the flexographic plate of printing unit 22.

Referring now to FIGURE 4, FIGURE 5 and FIGURE 6, the in-line inking/coating apparatus 10 includes a carriage assembly 58 which supports an applicator head 60. The applicator head 60 includes a hydraulic motor 62, a lower gear train 64, an upper gear train 65, an applicator roller 66 and a doctor blade assembly 68. The external peripheral surface of the applicator roller 66 is inserted into wetting contact with liquid coating material or ink contained in a reservoir 70. The reservoir 70 is continuously supplied with ink or coating which is circulated through the reservoir 70 from an off-press source by a pump (not illustrated). The hydraulic motor 62 drives the applicator roller 66 synchronously with the plate cylinder 32 and the blanket cylinder 34 in response to an RPM control signal from the press drive (not illustrated) and a feedback signal developed by a tachometer 72. While a hydraulic drive motor is preferred, an electric drive motor can be used.

The applicator roller 66 is preferably a fluid metering anilox roller which transfers measured amounts of printing ink or coating material onto the printing plate or

0935796.054404

blanket. The surface of an anilox roller is engraved with an array of closely spaced, shallow depressions referred as "cells". Ink or coating material from the reservoir 70 flows into the cells as the anilox roller turns through the reservoir. The transfer surface of the anilox roller is scraped with a doctor blade 73 to remove excess ink or coating. The ink or coating remaining on the anilox roller is the measured amounts contained within the cells.

The applicator roller 66 is cylindrical and may be constructed in various diameters and lengths, containing cells of various sizes and shapes. The volumetric capacity of an anilox roller is established during manufacturing and is dependent upon the selection of cell size, shape and number of cells per unit area. Depending upon the intended application, the cell pattern may be fine (many small cells per unit area) or coarse (fewer larger cells per unit area).

By applying the ink or coating material through the inking/coating applicator head 60, more ink or coating material can be delivered to the sheet S as compared with the inking roller train of a lithographic printing unit. Moreover, color intensity is stronger and more brilliant because the flexographic ink is applied at a much larger film thickness than can be applied by the lithographic process and is not diluted by dampening solution.

The inking/coating applicator head 60 includes side frame members 74, 76 that support the applicator roller 66, gear train 64, gear train 65, doctor blade

09315796-051404

assembly 68 and the drive motor 62. The applicator roller 66 is supported at opposite ends on a lower cradle formed by a pair of end plates 78, 80 which hold the applicator roller 66 in parallel alignment with the blanket cylinder 34 (FIGURE 5). The side frames 74, 76 are also provided with an upper cradle formed by a pair of side plates 82, 84 which are vertically spaced with respect to the lower side plates 78, 80. Each cradle has a pair of sockets 79, 81 and 83, 85, respectively, for holding the applicator roller 66 for spot coating or inking engagement against the plate P of the plate cylinder 32 (FIGURE 4) or the blanket B of the blanket cylinder 34.

Preferably, the applicator roller 66 for the upper cradle (plate) position is an anilox roller having a resilient transfer surface. In the dual cradle arrangement, the press operator can quickly change over from blanket inking/coating and plate inking/coating with minimum press down time, since it is only necessary to remove and reposition or replace the applicator roller 66, and wash-up the doctor blade assembly if changing from ink to coating or vice versa. The capability to selectively operate in either the flexographic mode or the lithographic mode and to print or coat from either the plate or blanket position is referred to herein as the "LITHOFLEX" process.

Referring again to FIGURE 2 and FIGURE 3, the applicator head 60 is supported by the carriage assembly 58 in a cantilevered, pivotal arrangement which allows the dual cradle inking/coating apparatus 10 and a single cradle

09345796 654401  
TOP SECRET

The cantilevered support arms are pivotally mounted on the printing tower by pivot blocks 92, 94, respectively. The hub portions 88A, 90A are journaled for rotation on pivot shafts 96, 98, respectively. The pivot blocks 92, 94 are securely fastened to the tower 14D, so that the carriage assembly 86 is pivotally suspended from the pivot shafts 96, 98 in a cantilevered Ferris support arrangement. The shank portions 88B, 90B are pivotally coupled to the pivot shaft 77, so that the carriage assembly 58 and the applicator head 60 are capable of independent rotation with respect to each other and with respect to the pivot shaft 77. By this arrangement, the applicator head 60 is pivotally suspended from the pivot shaft 77, and remains in an upright orientation as the support arms rotate from the operative position to the fully retracted position, and vice versa.

25                    Thus, the cradles 78, 80 and 82, 84 position the applicator roller 66 in vertical and horizontal alignment with the plate cylinder or blanket cylinder when the applicator head is extended to the operative position, for



example as shown in FIGURE 4 and FIGURE 5. Moreover, because of the transverse relationship between the hub portion and shank portion of the support arms, the applicator head 60 and carriage assembly 58 are capable of rotating through a Ferris arc without touching the adjacent printing tower. This makes it possible to install the inking/coating apparatus 10 on any intermediate printing unit tower (T2, T3), and as well as on the first printing unit tower T1 and the last printing unit tower T4. Additionally, when the inking/coating unit 10 is in the operative position, the lateral projection of the applicator head 60 into the interstation space between printing units is minimized. This assures virtually unrestricted operator access to the interstation space between adjacent printing units when the applicator head is engaged in the operative position, and completely unrestricted access when the carriage assembly 58 is retracted.

Rotation of the carriage assembly 58 is counter-clockwise from the retracted, idle position (shown in phantom in FIGURE 1) to the operative position (FIGURE 4 and FIGURE 5). The carriage assembly 58 can be adapted for clockwise rotation from the retracted position to the operative position for engagement of the applicator roller to either the plate or the blanket on the dampener side of the tower, assuming that access to the plate and blanket is not restricted by dampener rollers or the like.

Rotational movement of the support arms 88, 90 is assisted by counterweights 100, 102 which are secured to

09315796-051401

the support arms, respectively, for concurrent rotation with respect to the pivot blocks 92, 94. With the passive assistance of the counterweights, the press operator can easily move the inking/coating assembly 10 from the engaged operative position as shown in FIGURE 4 to the fully retracted, idle position as shown in phantom in FIGURE 1. Preferably, rotation of the carriage assembly 58 is assisted by a torsion spring, electric motor or hydraulic motor.

10           The inking/coating apparatus 10 is releasably locked into the operative position as shown in FIGURE 4 by releasable latch couplings 103, 105 that secure the support arms 88, 90 to the press side frames 14, 15, respectively, of the printing unit tower T4 in the operative position.

15   Coating engagement of the applicator roller 66 against the blanket cylinder 34 is produced by power actuators, preferably pneumatic cylinders 104, 106 which have extendable/retractable power transfer arms 104A, 106A, respectively. The pneumatic cylinder 104 is pivotally

20   coupled to the support arm 88 by a pivot linkage 108, and the second pneumatic cylinder 106 is pivotally coupled to the support arm 90 by a pivot linkage 109. In response to actuation of the pneumatic cylinders 104, 106, the power transfer arms are retracted. As the transfer arms retract,

25   the inking/coating head 60 is rotated counterclockwise on the pivot shaft 77, thus moving the applicator roller 66 into coating engagement with the blanket cylinder 34.

0944706 08444

The pivot linkage 108 includes a bell crank 111 which is mounted for pivotal movement on a pin 113. The pin 113 is supported by a clevis plate 115 which is attached to the support arm 88. One end of the bell crank  
5 is pivotally coupled to the actuator arm 104A, and a cam roller 117 is mounted for rotation on its opposite end.

The cam roller 117 is engagable against an adjustable stop 119 which is rigidly secured to the side plate 74. Counterclockwise shifting of the handle H moves  
10 a cam follower 121 into a latch pocket 123 of a receiver block 125 as the cam roller 117 is moved into engagement with the adjustable stop 119 in the interlocked, operative position. Referring to FIGURE 4, FIGURE 5 and FIGURE 6, the receiver block 125 is secured to the delivery side of  
15 the printing unit tower by machine screws.

When the plate P goes on impression, power is applied to the pneumatic actuator 104 and the power transfer arm 104A retracts, thus causing the bell crank 111 to rotate counterclockwise about the pin 113. The torque  
20 applied by the pneumatic actuator 104 is transmitted to the applicator head 60 through the cam roller 117 and the adjustable stop 119. Counterclockwise movement of the applicator head 60 relative to the support shaft 77 carries the applicator roller 66 into engagement with the plate P.

The adjustable stop 119 has a threaded bolt 119A  
25 which is engagable with the cam roller 117. The striking point of engagement is preset so that the applicator roller 66 is properly positioned for engagement with the plate P

00345796-054101  
TOP SECRET

or blanket B in the operative position when the applicator head 60 is interlocked with the press frame 14 and the printing unit goes on impression.

Referring to FIGURE 5, an inking/coating apparatus 110 having a single head is illustrated. The construction of this alternative embodiment is identical in all respects with the dual head arrangement, with the exception that only a single gear train and a single cradle for holding the applicator roller is provided. In both  
5       embodiments, the inking/coating head 60 remains upright as it swings through an arc, comparable to the movement of a Ferris wheel. Because of the upright orientation of the inking/coating head 60 as it moves between the extended and retracted positions, the usual platform spacing between  
10       printing unit towers provides adequate clearance to permit extension and retraction of the carriage assembly 58 without interference with operator access to the printing units. This is a significant advantage in that it permits the in-line inking/coating apparatus 10 to operate effec-  
15       tively in the interstation space between any adjacent printing units, and without blocking or obstructing access to the cylinders of the printing units when the inking/coating apparatus is in the retracted position (as indicated in phantom in FIGURE 1).

Moreover, when the in-line inking/coating  
20       apparatus is in the fully retracted position, the applicator roller 66 is conveniently positioned on the dampener side of the printing unit for inspection, clean-up or  
25

0915796-031401  
107750 9625760

replacement. Additionally, the doctor blade assembly is also conveniently positioned for inspection, removal, adjustment or clean-up. Also, the doctor blade reservoir and coating circulation lines can be cleaned while the press is running as well as when the press has been stopped for change-over from one type of ink or coating material to another.

When the inking/coating apparatus is used for applying an aqueous ink or an aqueous coating material, the water component on the freshly printed sheet S is evaporated by a high velocity, hot air interstation dryer and high volume heat and moisture extractor units 112 and 114, as shown in FIGURE 1, FIGURE 4 and FIGURE 5. The dryer/extractor units 112 and 114 are oriented to direct high velocity heated air onto the freshly printed/coated sheets as they are transferred by the interunit and the intermediate transfer cylinders 36, 40. By this arrangement, the freshly printed aqueous ink or coating material is completely dry before the sheet is overprinted in the next printing unit.

The high velocity, hot air dryer and high performance heat and moisture extractor units 112, 114 utilize high velocity air jets which scrub and break-up the moist air level which clings to the surface of each freshly printed sheet. Within each dryer, high velocity air is heated to a high temperature as it flows across a resistance heating element within an air delivery baffle tube. High velocity jets of hot air are discharged through

multiple airflow apertures through an exposure zone Z (FIGURE 4 and FIGURE 5) onto the freshly printed/coated sheet S as it is transferred by the transfer cylinder 36 and intermediate transfer cylinder 40, respectively. Each  
5 dryer assembly includes a pair of air delivery dryer heads which are arranged in spaced, side-by-side relation as shown in FIGURE 4 and FIGURE 5.

The high velocity, hot moisture-laden air displaced from each freshly printed sheet is extracted from  
10 the dryer exposure zone Z and completely exhausted from the printing unit by the high volume extractors. Each extractor head includes a manifold coupled to the dryer heads and draws the moisture, volatiles and high velocity hot air through a longitudinal gap between the dryer heads.  
15 According to this arrangement, each printed sheet is dried before it is run through the next printing unit.

The water-based inks used in flexographic printing dry at a relatively moderate drying temperature provided by the interstation high velocity hot air dry-  
20 ers/extractors 112, 114. Consequently, print quality is substantially improved since the aqueous ink is dried at each printing unit before it enters the next printing unit. Moreover, back-trapping on the blanket of the next printing unit is completely eliminated. This interstation drying  
25 arrangement makes it possible to print aqueous inks such as metallic ink and opaque white ink at one printing unit, and then overprint at the next printing unit.

0034796 DE 101

00315796-051101

This arrangement also permits the first printing unit to be used as a coater in which an aqueous coating is applied to low grade paper, for example recycled paper, to trap and seal in lint, dust, spray powder and other debris and provide a smoother, durable surface that can be overprinted in the next printing unit. The first down coating seals the surface of the low grade, rough substrate and improves overprinted dot definition while preventing strike-through and show-through. A UV-curable protective and/or decorative coating can be applied over the first down overprinted (aqueous) coating in the last printing unit.

Preferably, the applicator roller 66 is constructed of metal or ceramic when it is used for applying a coating material to the blanket B on the cylinder 34. When the applicator roller 66 is applied to the plate, it is preferably constructed as an anilox roller having a resilient transfer surface for engaging a flexographic printing plate. Suitable resilient roller surface materials include Buna N synthetic rubber and EPDM (terpolymer elastomer).

It will be appreciated that the inking/coating apparatus 10 is capable of applying a wide range of ink types, including fluorescent (Day Glo), pearlescent, metallics (gold, silver and other metallics), glitter, scratch and sniff (micro-encapsulated fragrance), scratch and reveal, luminous, pressure-sensitive adhesives and the like.

The press operator can eliminate the dampener roller assembly altogether, and the inking/coating apparatus 10 can selectively apply aqueous inks and coatings to a flexographic or waterless printing plate and the blanket. Moreover, overprinting of the aqueous inks and coatings can be carried out in the next printing unit since the aqueous inks and coatings are completely dried by the high velocity, hot air interstation dryer and high volume heat and moisture extractor assembly.

10 The aqueous inks and coatings as used in the present invention contain colored pigments and/or soluble dyes, binders that fix the pigments onto the surface of the printed sheet, and waxes, defoamers and thickeners. Aqueous printing inks predominantly contain water as a solvent, diluent and/or vehicle. The thickeners which are preferred include algonates, starch, cellulose and its derivatives, for example cellulose esters or cellulose ethers and the like. Coloring agents including organic as well as inorganic pigments may be derived from dyes which are insoluble in water. Also, the printing ink may contain water and can be predominantly glycol or the like, with the pigment being bound by an appropriate resin. When metallic inks are printed, the cells of the anilox roller must be appropriately sized to prevent the metal particles from getting stuck within the cells. The cell size is critical, and for metallic gold ink, the anilox roller should have a screen line count in the range of 175-300 lines per inch (69-118 lines per cm).

0015736 05404  
FOUO 04/24/80



The inking/coating apparatus 10 can also apply UV-curable inks and coatings. If UV-curable inks and coatings are utilized, ultra-violet dryers/extractors are installed adjacent the high velocity hot air dryer/extractor units 112, 114, respectively.

It will be appreciated that the inking/coating apparatus 10 described herein makes it possible to selectively operate a printing unit in either the flexographic printing mode or the lithographic printing mode, while also providing the capability to print or coat from either the plate or blanket position. The dual cradle support arrangement of the present invention makes it possible to quickly change over from inking/coating at the blanket cylinder position to inking/coating at the plate cylinder position with minimum press down-time, since it is only necessary to remove and reposition or replace the applicator roller 66 while the printing/inking apparatus is in the retracted position.

Moreover, the press operator may elect to spot or overall coat with aqueous ink/coating from the plate during one job, and then spot and/or overall coat from the blanket during the next job. Since the doctor blade assembly can be flushed and washed-up quickly and the applicator roller can be replaced quickly, it is possible to spot coat or overall coat from the plate position or the blanket position with aqueous inks or coatings during the first press run and then spot coat or overall coat with UV-curable inks or coatings from the plate position or from

00345796 054404  
TOP SECRET

the blanket position during the next press run. The inking/coating apparatus 10 is completely out of the way in the retracted position; consequently, the doctor blade reservoir and supply lines can be flushed and washed-up by automatic wash-up equipment while the printing unit is printing another job.

The positioning of the applicator head and roller assembly relative to the plate and blanket is repeatable to a predetermined, preset impression position. Consequently, no printing unit adjustment or alteration is required, except for flushing the doctor blade assembly and cleaning or replacing the applicator roller to accommodate a different kind of ink or coating material. Although manual extension and retraction have been described in connection with the exemplary embodiment, extension to the operative position and retraction to a non-operative idle position can be carried out automatically by hydraulic or electric motor servomechanisms.

The Ferris wheel support arrangement allows the inking/coating apparatus to operate effectively in the interstation space between any adjacent printing units, as well as on the first or last printing units of the press, without blocking or obstructing the interstation space or restricting operator access to the cylinders of any of the printing units.

Finally, because the inking/coating apparatus of the present invention is mounted on a printing unit tower and is extendable to the operative position without

0015746-001

requiring adjustment or alteration of the printing unit cylinders, it can be used for applying printing ink or coating material to the blanket cylinder of a rotary offset web press, or to the blanket of a dedicated coating unit.

00315796 DE 1 101  
FOR INFO 06/25/60

CLAIMS:

1. Inking/coating apparatus (10) for use in a printing press (12) of the type having a printing unit (22, 24, 26, 28) on which a plate cylinder (32), a blanket cylinder (34) and an impression cylinder (36) are mounted for rotation, wherein the inking/coating apparatus is characterized by:

an applicator head (60) for applying ink or coating material to a plate (P) mounted on the plate cylinder or to a blanket (B) mounted on the blanket cylinder, either separately or simultaneously when the inking/coating apparatus is in an operative position relative to the plate and blanket cylinders; and,

a carriage assembly (58) for moving the applicator head to the operative position in which the applicator head is disposed laterally adjacent to the plate and blanket cylinders and for moving the applicator head from the operative position to a retracted position in which the applicator head is elevated with respect to the plate and blanket cylinders.

2. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) is characterized by:

a support arm (88, 90) having a first end portion (88A) constructed for pivotal attachment to the

00315796 054104

printing unit and having a second end portion (88B) pivotally coupled to the applicator head (60), the applicator head being movable on the support arm to the operative position.

5                   3.    Inking/coating apparatus (10) as set forth in claim 1, characterized in that a counterweight (100, 102) is coupled to the carriage assembly.

10                   4.    Inking/coating apparatus (10) as set forth in claim 1, wherein the applicator head (60) is characterized by:

                  a doctor blade assembly (68) having a reservoir (70) for receiving ink or liquid coating material; and,

15                   an applicator roller (66) coupled to the doctor blade assembly in fluid communication with the reservoir, the applicator roller being engagable with a printing plate (P) on the plate cylinder or with a blanket (B) on the blanket cylinder when the applicator head (60)  
20 is in the operative position.

                  5.    Inking/coating apparatus (10) as set forth in claim 4, characterized in that the applicator roller (66) is an anilox roller having a resilient transfer  
25 surface.

00345796 64104  
101149 967460

6. Inking/coating apparatus (10) as set forth in claim 1, characterized in that:

5 a power actuator (104, 106) is movably coupled to the applicator head (60), the power actuator having a power transfer arm (104A, 106A) which is extendable and retractable; and,

10 movement converting apparatus (108) is coupled to the power transfer arm for converting extension or retraction movement of the power transfer arm into pivotal movement of the applicator head (60) relative to the carriage assembly.

7. Inking/coating apparatus (10) as set forth in claim 6, wherein the movement converting apparatus (108) is characterized by:

15 a bell crank plate (111) having a first end portion coupled to the power transfer arm and having a second end portion for engaging a stop member;

a stop member (119) secured to the applicator head (60); and,

20 a clevis plate (115) secured to the carriage assembly (58) and pivotally coupled to the bell crank plate.

8. Inking/coating apparatus (10) as set forth in claim 1, wherein the applicator head (60) is characterized by:

25

00345796-064104

first and second side frame members (74, 76)  
pivotally coupled to the carriage assembly (58);

a doctor blade assembly mounted on the first  
and second side frame members, the doctor blade assembly  
5 including a reservoir (70) for receiving ink or liquid  
coating material;

a cradle assembly (78, 80), (82, 84) mounted  
on the first and second side frame members, respectively;

an applicator roller (66) mounted for  
10 rotation on the cradle assembly and coupled to the doctor  
blade assembly for rolling contact with ink or coating  
material in the reservoir, the applicator roller being  
engagable with a printing plate (P) on the plate cylinder  
(32) or with a blanket (B) on the blanket cylinder (34)  
15 when the applicator head (60) is in the operative position;  
and,

a drive motor (62) coupled to the applicator  
roller for rotating the applicator roller.

9. Inking/coating apparatus (10) as set forth  
20 in claim 8, characterized in that:

the cradle assembly (79, 80) has first and  
second sockets (79, 81) disposed on the first and second  
side frame members respectively; and,

the applicator roller (66) is mounted for  
25 rotation on the first and second sockets.

0315796 00110

10. Inking/coating apparatus (10) as set forth  
in claim 8, characterized in that

the cradle assembly (78, 80), (82, 84)  
includes first and second sockets (79, 81) disposed on the  
5 first and second side frame members, respectively, and  
third and fourth sockets disposed on the first and second  
side frame members, respectively; and,

the applicator roller (66) is selectively  
mountable for rotation on either the first and second  
10 sockets or on the third and fourth sockets for applying ink  
or coating material to either the plate or blanket when the  
applicator head is in the operative position.

11. Inking/coating apparatus (10) as set forth  
in claim 1, wherein the applicator head (60) is character-  
15 ized by:

a first cradle (78, 80) for supporting an  
applicator roller (66) for engagement with the plate when  
the inking/coating apparatus is in the operative position;  
and

20 a second cradle (82, 84) for supporting an  
applicator roller (66) for engagement with the blanket (B)  
when the inking/coating apparatus is in the operative  
position.

12. Inking/coating apparatus (10) as set forth  
25 in claim 1, wherein the carriage assembly is characterized  
by:

005796 0004  
000000 000000



a support arm (88, 90) having a first end portion pivotally coupled to the printing unit (88A, 90A) and having a second end portion (88B, 90B);

a common pivot shaft (77) on which the support arm second end portion and the inking/coating apparatus are pivotally mounted; and,

male and female latch members (103, 105) coupled between the common pivot shaft and the printing unit, with one of the latch members being secured to the common pivot shaft and the other latch member being constructed for attachment onto the printing unit, the latch members being mateable in interlocking engagement when the applicator head (60) is in the operative position.

13. Inking/coating apparatus (10) as set forth in claim 1, wherein the applicator head (60) and the printing unit are characterized by:

male and female latch coupling members (103, 105) mounted on the carriage assembly (58) and on the printing unit for releasably latching the carriage assembly in interlocking engagement with the printing unit when the applicator head is in the operative position.

14. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) is characterized by an elongated shank portion (88B, 90B) and a hub portion (88A, 90A), the elongated shank portion being pivotally coupled to the applicator head (60) and the hub

00315796 DEFI 01

portion being constructed for pivotal attachment onto the printing unit.

15. A rotary offset printing press (12) having first and second printing units (22, 24) and the ink-  
5 ing/coating apparatus (10) of claim 1 is movably coupled to the first printing unit (22) as set forth in claim 1, characterized by:

a dryer (112) mounted on the first printing unit adjacent the impression cylinder (36) of the first  
10 printing unit for discharging heated air onto a freshly printed substrate while the freshly printed substrate is in contact with said impression cylinder.

16. A rotary offset printing press (12) as defined in claim 15, characterized in that:

15 an extractor (112E) is disposed adjacent the dryer for extracting hot air, moisture and volatiles from an exposure zone (Z) between the dryer and the freshly printed substrate.

17. A rotary offset printing press (12) as defined in claim 15, characterized in that:

20 an intermediate transfer cylinder (40) is coupled in sheet transfer relation with the impression cylinder (36) of the first printing unit (22); and,

an interstation dryer (114) is disposed  
25 adjacent the intermediate transfer cylinder for discharging

00345796 DEFI 01

heated air onto a freshly printed or coated substrate after it has been transferred from the impression cylinder of the first printing unit and while it is in contact with the intermediate transfer cylinder (40).

5                   18. A method for rotary offset printing in a printing press (12) of the type including first and second rotary offset printing units (22, 24), and using aqueous or UV-curable printing ink or coating material in the operation of at least the first printing unit, characterized by  
10 the following steps performed at each printing unit in succession:

                  spot or overall coating a plate (P) with aqueous ink/aqueous coating material or UV-curable ink/UV-curable coating material;

15                   spot and/or overall coating a blanket (B) with aqueous ink/aqueous coating material or UV-curable ink or UV-curable coating material;

                  transferring the printing ink or coating material from the printing plate (P) to the blanket (B);

20                   transferring the inked or coated image from the blanket to a substrate (S) as the substrate is transferred through the nip between the impression cylinder (36) and the blanket (B); and,

                  drying the ink or coating material on the  
25 freshly printed substrate before the substrate is subsequently processed.

003445796 054404  
FOI 90-00000000000000

19. A method for rotary offset printing as defined in claim 18, wherein the drying step is characterized by:

5       discharging high velocity, heated air onto the freshly printed/coated substrate (S) while the freshly printed/coated substrate is in contact with the impression cylinder (36) of the first printing unit (22).

20. A method for rotary offset printing as defined in claim 18, characterized by the steps:

10       transferring the freshly printed substrate (S) from the first printing unit (22) to an intermediate transfer cylinder (40); and,

      drying the freshly printed substrate while it is in contact with the intermediate transfer cylinder.

15       21. A method for rotary offset printing as defined in claim 18, characterized by the step:

      extracting hot air, moisture and volatiles from an exposure zone (Z) above the freshly printed/coated substrate (S) while the freshly printed/coated substrate is  
20       in contact with the impression cylinder (36).

22. A method for rotary offset printing as defined in claim 18, characterized by the steps:

      applying a primer coating of an aqueous coating material or UV-curable coating material to a  
25       substrate (S) in the first printing unit (22); and,

00245796 054104

drying the primer coating on the substrate before the substrate is processed in the second printing unit.

00345706 054404

"RETRACTABLE INKING/COATING APPARATUS  
HAVING FERRIS MOVEMENT BETWEEN PRINTING UNITS"

ABSTRACT

A retractable in-line inking/coating apparatus (10) selectively applies either spot or overall ink/coating material to a blanket (B) or flexographic plate (P) on a blanket cylinder (34), or spot or overall ink/coating to a flexographic printing plate (P) on a plate cylinder (32) in a rotary offset printing press (12). The inking/coating apparatus is pivotally mounted on a printing unit (22, 24, 26, 28) or dedicated coating unit, and is extendable into and retractable out of an operative inking/coating position by a carriage assembly (58) which is pivotally coupled to the printing unit. Because of the pivotal support provided by a cantilevered support arm (88, 90), the inking/coating apparatus is extended and retracted through a Ferris wheel arc between adjacent printing units.

FIG. 1

00345746 154101  
TOP SECRET




FIG. 1




FIG. 2




FIG. 3

09315796 054101



00345796 054104




FIG. 4




FIG. 10 is a detailed schematic diagram of a mechanical assembly, possibly a printing press or a similar industrial machine. The diagram shows a complex arrangement of gears, levers, and structural components. Key elements include:

- 60**: The main frame or housing of the assembly.
- 62**: A large circular component, likely a motor or a flywheel, at the bottom left.
- 72**: A small gear or pulley connected to the main drive.
- 64**, **65**, **68**, **70**, **73**, **79**: Various intermediate gears and shafts forming a transmission system.
- 78**: A horizontal shaft or lever at the bottom right.
- 81**, **82**: Components near the center-right, possibly related to paper handling or registration.
- 88**, **88B**: Vertical structural supports or guides.
- 103**, **104**, **104A**, **108**, **113**, **115**, **117**, **119**, **119A**: A linkage mechanism involving multiple pivots and rods, connecting different parts of the machine.
- 121**, **123**, **125**: Small rollers or guides positioned vertically.
- P**, **B**: Large curved surfaces, likely representing the printing cylinders or drums.
- T4**: A label for the top edge of the main frame.
- H**: A label for a specific part of the linkage mechanism.

The diagram uses dashed lines to indicate the rotational paths of several gears and the movement of certain components, illustrating the kinematic sequence of the machine.

FIG. 6

# MEWBURN ELLIS


INTELLECTUAL PROPERTY  
PATENTS TRADEMARK DESIGN

7th June 1996

European Patent Office,  
Postbus 5818,  
2280 HV RIJSWIJK (ZH),  
The Netherlands

Chartered Patent Agents  
European Patent Attorneys  
Trade Mark Agents

York House  
23 Kingsway  
London WC2B 6HP



Tel 0171 240 4405  
Telex 22762 Patent G  
Fax 0171 240 9339  
Fax 0171 240 0652 (G4)  
ANL DX 37956 Kingsway WC2

**Partners**  
H A Gura  
D C Harrison  
I M Armitage  
H C E Paget  
M F Ford  
T R Calderbank  
S J Linn  
G P Stoner  
C J O'Brien  
S M Walton  
N J Hackney

**Assisted by**  
R E Sody  
A R Brewster  
J I Christensen  
R Coleiro  
M G Foster  
M P Freeman  
R S Gimsa  
A Hamilton  
S J Hill  
A J Weyant  
D J Webb  
S J Kiddle  
J M Madef  
M M T Madef  
A M Nicholls  
M J Sarcanton  
I A Stuart  
D A Taylor  
R M Thornley

**Consultant**  
E Armitage CB

Dear Sirs

European Patent Application No. 96303136.4  
**DEMOORE, HOWARD WARREN**  
**Our Ref: HAG/FP5233994**

To complete the filing formalities on this application, we now present herewith a certified copy of the priority US application.

Yours faithfully


H A GURA  
AUTHORISED REPRESENTATIVE

HG/GC

Encl.

PRIO 015

Offices also at Bristol Cambridge  
Manchester Newcastle



# THE UNITED STATES OF AMERICA

TO ALL TO WHOM THESE PRESENTS SHALL COME:

UNITED STATES DEPARTMENT OF COMMERCE  
United States Patent and Trademark Office

May 6, 1996

THIS IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY FROM THE RECORDS OF THE UNITED STATES PATENT AND TRADEMARK OFFICE OF THOSE PAPERS OF THE BELOW IDENTIFIED PATENT APPLICATION THAT MET THE REQUIREMENTS TO BE GRANTED A FILING DATE UNDER 35 USC 111.

APPLICATION NUMBER: 08/435,798 ✓

FILING DATE: May 4, 1995 ✓



By Authority of the  
COMMISSIONER OF PATENTS AND TRADEMARKS

*K. White*

K. WHITE

Certifying Officer

PATENT APPLICATION SERIAL NO. 09 435798

U.S. DEPARTMENT OF COMMERCE  
PATENT AND TRADEMARK OFFICE  
FEE RECORD SHEET

09315798-054101

110 MM 05/19/95 08435798

1 201 633.00 CK B6012

PTO-1556  
(5/87)

SPECIFICATION

accompanying

Application for Grant of U.S. Letters Patent

JOINT

INVENTORS:

Ronald M. Rendleman  
4331 Royal Ridge  
Dallas, Texas 75229

Howard W. DeMoore  
10954 Shady Trail  
Dallas, Texas 75220

John W. Bird  
1514 Iroquois Circle  
Carrollton, Texas 75007

TITLE: "RETRACTABLE INKING/COATING APPARATUS HAVING FERRIS  
MOVEMENT BETWEEN PRINTING UNITS"

Field of the Invention

1 This invention relates to sheet-fed or web-fed, rotary  
2 offset or flexographic printing presses, and more particularly, to  
3 a new and improved inking/coating apparatus for the in-line  
4 application of printing inks or protective or decorative coatings  
5 to sheets or web.

6 Background of the Invention

7 Conventional sheet-fed, rotary offset printing presses  
8 typically include one or more printing units through which  
9 individual sheets are fed and printed with wet ink. After the  
10 last printing unit, the sheets are transferred by a delivery  
11 conveyor to the delivery end of the press where the freshly  
12 printed sheets are collected and stacked. In a typical sheet-fed,  
13 rotary offset printing press such as the Heidelberg Speedmaster  
14 line of presses, the delivery conveyor includes a pair of endless  
15 gripper chains carrying gripper bars and gripper fingers which  
16 grip and pull freshly printed sheets from the last impression  
17 cylinder and convey the sheets to the sheet delivery stacker.

00315796 054404  
FOUO 0675560

1           Since the inks used with rotary offset printing presses  
2 typically remain wet and tacky for some time after printing,  
3 special precautions must be taken to insure that the freshly  
4 printed sheets are not marked or smeared as the sheets are  
5 transferred from one printing unit to another, and while being  
6 conveyed to the sheet delivery stacker. The printed surface of  
7 the sheet dries relatively slowly and can be smeared during  
8 subsequent transfer between printing units. In order to reduce  
9 smearing and offsetting, spray powder is applied on the printed  
10 sheet.

11           In some printing applications, offset and smearing are  
12 prevented by applying a protective and/or decorative coating over  
13 all or a portion of the freshly printed sheets. Some coating  
14 solutions include varnish, lacquer, dye, moisturizers and ink.  
15 Such coatings are formed of a UV-curable or water-dispersed resin  
16 applied as a liquid solution or emulsion over the freshly printed  
17 sheets to protect the ink and improve the appearance of the  
18 freshly printed sheets. Such coatings are particularly desirable  
19 when decorative or protective finishes are required such as in the  
20 production of posters, record jackets, brochures, magazines,  
21 folding cartons and the like. The coating is permeable to oxygen  
22 to permit drying of the ink. In cases where a liquid coating is  
23 to be applied, the coating operation is carried out after the last  
24 color ink has been printed. In some cases, it is desirable to  
25 spot coat from the printing plate. For both operations, the  
26 coating is most desirably performed by an in-line coater.

27           In printing presses having flexographic printing plates,  
28 an aqueous ink is used, for example metallic (gold) ink and opaque  
29 white ink, both of which can be overprinted at the next printing  
30 unit. An advantage of flexographic printing is that no dampening  
31 unit is required. The flexographic printing plate has a raised  
32 image surface (relief). Colors are stronger when flexographic  
33 inks are used because they are not diluted by dampening solution.



00315796-054104  
TOTAL 96251260

1     Description of the Prior Art

2             Various arrangements have been made for applying the  
3     coating as an in-line printing operation by using the last  
4     printing unit of the press as the coating application unit. For  
5     example, in U.S. Patents 4,270,483, 4,685,414 and 4,779,557, there  
6     are disclosed coating apparatus which can be moved into position  
7     to allow the blanket cylinder of the last printing unit of a press  
8     to be used to apply a coating material to the sheets. In U.S.  
9     Patent 4,796,556 and U.S. Patent 4,841,903 there is disclosed a  
10    coating apparatus which can be selectively moved between the  
11    blanket cylinder or the plate cylinder of the last printing unit  
12    of the press so that the last printing unit can only be used for  
13    coating purposes. However, when coating apparatus of these types  
14    are used, the last printing unit cannot be used to apply ink to  
15    the sheets, but rather can only be used for the coating operation.  
16    Thus, while coating with these types of in-line coating apparatus,  
17    the press loses the capability of printing its full range of  
18    colors since the last printing unit is converted to a coating  
19    unit.

20            Proposals for overcoming the problem of the loss of a  
21    printing unit when in-line coating is desired have also been made,  
22    such as that set forth in U.S. Patent 4,934,305 which discloses a  
23    coating apparatus having a separately timed applicator roller  
24    positioned to apply the coating material to the freshly printed  
25    sheet while the sheet is on the last impression cylinder of the  
26    press. This is said to allow the last printing unit to print and  
27    coat simultaneously, so that no loss of a printing unit capability  
28    results. Another approach to providing a coating unit without  
29    losing the printing capabilities of the last printing unit is to  
30    provide a totally separate coating unit downstream of the last  
31    printing unit so that the coating is applied to the sheets after  
32    the last printing unit. Such an arrangement is disclosed in U.S.  
33    Patents 4,399,767, 4,706,601 and 5,176,077.

34            In an effort to reduce costs and maintain flexibility in  
35    adapting the printing press to different jobs, coating apparatus

00315796-051101

1 has been provided that can be selectively engaged with the plate  
2 cylinder or blanket cylinder to carry out the coating operation,  
3 and disengaged so that the last printing unit can be used for  
4 offset printing when coating is not required. Examples of coaters  
5 which are selectively engagable with either the plate cylinder or  
6 the blanket cylinder are disclosed in U.S. Patent 4,615,293  
7 (Jahn), U.S. Patent 5,107,790 (Sliker et al.) and U.S. Patent  
8 4,841,903 (Bird).

9 The coater of U.S. Patent 4,615,293 includes two  
10 applicator rollers, both disposed on the dampening side of the  
11 plate cylinder and blanket cylinder for carrying out spot and  
12 blanket coating operations as desired. The coater of U.S. Patent  
13 5,107,790 is retractable along an inclined rail for extending and  
14 retracting a coater head into engagement with either the plate  
15 cylinder or the blanket cylinder. Because of its size, the  
16 rail-retractable coater can only be installed between the last  
17 printing unit of the press and the delivery stacker, and cannot be  
18 used at interstation positions. The coaters of Patent 4,615,293  
19 are located on the dampener side of the plate and blanket cylin-  
20 ders, thus requiring removal of the dampening unit to make room  
21 for the doctor blade head and applicator rollers. Consequently,  
22 the last printing unit of the press is converted into a coating  
23 unit, resulting in the loss of the printing capability of that  
24 printing unit.

25 It will be appreciated that the time required to  
26 reconfigure a press for coating or non-coating is non-productive  
27 and costly. Accordingly, there is a need for a coating apparatus  
28 which minimizes the time to clean-up from one printing run and set  
29 up and run the next job. Where consecutive jobs require the same  
30 type of coating, particularly blanket coating, it may not be  
31 necessary to clean-up the coater between jobs. However, the  
32 coating cannot be allowed to dry on the rollers. Therefore,  
33 especially when switching from blanket to spot coating or vice  
34 versa, or if there is a delay between jobs, it is necessary to  
35 wash-up the coater after each job is completed.

00345796 054404

1 In addition, wash-up is necessary when switching between  
2 different coating compositions, such as aqueous and ultra-violet  
3 (UV) curable coatings. Such coatings are not interchangeable, and  
4 the coaters must be washed between applications of the different  
5 coating media. It is difficult to wash-up some coaters while the  
6 press is running. Moreover, the retractable coaters mentioned  
7 above occupy a large amount of press space and diminishes  
8 accessibility to the press. Elaborate equipment is needed for  
9 retracting the coater from the operative coating position to an  
10 out-of-the-way, inoperative position which reduces access to the  
11 printing unit.

12 A limitation on the use of flexographic printing plates  
13 and aqueous printing inks is that the freshly printed or coated  
14 sheets require hot air for drying. When applying an aqueous ink  
15 such as opaque white or metallic gold, it is necessary to dry the  
16 printed sheets between printing units before overprinting them.

17 Moreover, when utilizing lithographic printing inks, it  
18 is necessary to frequently stop the press and wash the blanket.  
19 Metallic ink in particular "piles" on the blanket and must be  
20 washed frequently.

#### 21 Objects of the Invention

22 Accordingly, the principal object of the present  
23 invention is to provide improved inking/coating apparatus which is  
24 capable of selectively applying ink or a coating material to a  
25 plate on a plate cylinder or a coating material to a blanket on a  
26 blanket cylinder of a printing press.

27 Another object of the present invention is to provide  
28 inking/coating apparatus of the character described which is  
29 extendable into inking/coating engagement with either a plate  
30 cylinder or a blanket cylinder, and which is retractable to a non-  
31 operative position to provide clear access to the cylinders of the  
32 printing unit.

33 A related object of the present invention is to provide  
34 inking/coating apparatus of the character described which is

00316796-051101  
TOP SECRET

1 capable of being used in an interstation position and does not  
2 interfere with access to the press.

3 Yet another object of the present invention is to  
4 provide inking/coating apparatus of the character described, which  
5 can be moved from an operative inking/coating engagement position  
6 to a non-operative, retracted position.

7 Still another object of the present invention is to  
8 provide inking/coating apparatus of the character described, which  
9 can be used for applying aqueous inks and coatings to a litho-  
10 graphic printing plate or a flexographic printing plate in a  
11 rotary offset press.

12 A related object of the present invention is to provide  
13 inking/coating apparatus of the character described, which is  
14 capable of applying aqueous coating at one printing unit and  
15 drying the coating before it reaches the next printing unit where  
16 it can be overprinted with aqueous ink or lithographic ink.

17 Another object of the present invention is to provide  
18 inking/coating apparatus for use on a multiple color rotary offset  
19 printing press that can apply ink or coating to the plate or  
20 blanket of a printing unit from a single applicator head.

21 A related object of the invention is to provide  
22 inking/coating apparatus of the character described, in which no  
23 printing unit adjustment or alteration is required when the  
24 applicator head is converted from plate to blanket operation and  
25 vice versa.

#### 26 Summary of the Invention

27 The foregoing objects are achieved by a retractable, in-  
28 line inking/coating apparatus which is mounted on a printing unit  
29 tower for pivotal, Ferris wheel type movement between an operative  
30 inking/coating position and a retracted, overhead position. The  
31 inking/coating apparatus includes an applicator head which extends  
32 into and retracts out of engagement with a plate on a plate  
33 cylinder or a blanket on a blanket cylinder. The inking/coating  
34 applicator head is positioned in parallel alignment with either

00315796-054103

1 the plate cylinder or the blanket cylinder by a carriage assembly  
2 which includes a cantilever support arm. The support arm is  
3 pivotally coupled between the inking/coating head and the printing  
4 unit tower. This cantilevered, pivotal mounting arrangement  
5 allows the inking/coating unit to be used between two printing  
6 units, as well as installed on the last printing unit of the  
7 press.

8 In the preferred embodiment, the applicator head  
9 includes vertically spaced pairs of cradle members with one cradle  
10 pair being adapted for supporting a metal or ceramic coating  
11 roller in alignment with a blanket cylinder, and the other cradle  
12 pair supporting a resilient anilox coating roller in alignment  
13 with the plate cylinder, respectively, when the applicator head is  
14 in the operative position. Because of the cantilevered, pivotal  
15 support provided by the support arm, the applicator head can be  
16 lifted and lowered through an arc, similar to Ferris wheel  
17 movement, in the limited space between adjacent printing units.  
18 When fully retracted, the coater and carriage assembly are lifted  
19 to an overhead position overlying the printing unit tower, thus  
20 providing complete access to the printing unit cylinders, without  
21 causing the printing unit to lose its printing capability. The  
22 inking/coating applicator roller can be inspected, cleaned or  
23 replaced and the doctor blade assembly can be washed-up automati-  
24 cally while the inking/coating apparatus is in the fully retracted  
25 position.

26 When the inking/coating apparatus is used in combination  
27 with a flexographic printing plate and aqueous ink or aqueous  
28 coating, the water component of the aqueous ink or coating on the  
29 freshly printed sheet is evaporated by a high velocity, hot air  
30 interstation dryer and a high volume heat and moisture extractor  
31 assembly so that the freshly printed ink or coating is completely  
32 dry before the sheet is printed on the next printing unit. This  
33 quick drying flexographic printing/coating arrangement permits a  
34 base coat of ink, for example opaque white or metallic ink (gold,  
35 silver or other metallics) to be applied in the first printing

00315796-054104

1 unit, and then overprinted by the lithographic process on the next  
2 printing unit.

3 Other features and advantages of the present invention  
4 will become more apparent from the following detailed description  
5 taken in conjunction with the accompanying drawings which  
6 disclose, by way of example, the principles of the present  
7 invention.

#### 8 Brief Description of the Drawings

9 FIGURE 1 is a schematic side elevational view of a  
10 sheet-fed, rotary offset printing press having inking/coating  
11 apparatus embodying the present invention;

12 FIGURE 2 is a perspective view of the printing press of  
13 FIGURE 1 in which a dual head inking/coating apparatus is in the  
14 operative coating position and a single head coater is in a  
15 retracted, overhead position;

16 FIGURE 3 is an enlarged simplified perspective view  
17 showing one side of the single head inking/coating apparatus of  
18 FIGURE 1 in the operative position;

19 FIGURE 4 is a simplified side elevational view showing  
20 the dual head inking/coating apparatus in the operative coating  
21 position for spot or overall coating from the blanket position;

22 FIGURE 5 is a simplified side elevational view showing  
23 the single head inking/coating apparatus in the operative coating  
24 position for spot or overall coating from the plate position; and,

25 FIGURE 6 is a simplified side elevational view of the  
26 dual head inking/coating apparatus of FIGURE 4, partially broken  
27 away, which illustrates the hydraulic drive assembly and doctor  
28 blade assembly.

#### 29 Detailed Description of the Preferred Embodiments

30 As used herein, the term "processed" refers to various  
31 printing methods which may be applied to either side of a  
32 substrate, including the application of UV-curable and aqueous  
33 inks and/or coatings. The term "substrate" refers to sheet or web

00345796-054104

1 material. Also, as used herein, the term "waterless printing  
2 plate" refers to a printing plate having non-image surface areas  
3 which are hydrophobic and also having image surface areas which  
4 are hydrophilic, wherein the non-image surface areas are charac-  
5 terized by a surface tension value which is less than the surface  
6 tension of aqueous ink, and the image surface areas are character-  
7 ized by a surface tension value which is greater than the surface  
8 tension of aqueous ink. "Flexographic" refers to flexible  
9 printing plates having a relief surface which is wettable by  
10 aqueous ink or coating material.

11 As shown in the exemplary drawings, the present  
12 invention is embodied in a new and improved in-line inking/coating  
13 apparatus, herein generally designated 10, for use in applying  
14 inks or protective and/or decorative coatings to sheets or webs  
15 printed in a sheet-fed or web-fed, offset rotary or flexographic  
16 printing press, herein generally designated 12. In this instance,  
17 as shown in FIGURE 1, the inking/coating apparatus 10 is installed  
18 in a four color printing press 12, such as that manufactured by  
19 Heidelberger Druckmaschinen AG of the Federal Republic of Germany  
20 under its designation Heidelberg Speedmaster 102V (40"). The  
21 press 12 includes a press frame 14 coupled at one end, herein the  
22 right end, to a sheet feeder 16 from which sheets, herein  
23 designated S, are individually and sequentially fed into the  
24 press, and at the opposite end, with a sheet delivery stacker 20  
25 in which the freshly printed sheets are collected and stacked.  
26 Interposed between the sheet feeder 16 and the sheet delivery  
27 stacker 20 are four substantially identical sheet printing units  
28 22, 24, 26 and 28 which can print different color inks onto the  
29 sheets as they are transferred through the press 12. The printing  
30 units are housed within printing towers T1, T2, T3 and T4 formed  
31 by side frame members 14, 15.

32 As illustrated, the printing units 22, 24, 26 and 28 are  
33 substantially identical and of conventional design. The first  
34 printing unit 22 includes an in-feed transfer cylinder 30, a plate  
35 cylinder 32, a blanker cylinder 34 and an impression cylinder 36,

09315796 054104

1 all supported for rotation in parallel alignment between the press  
2 side frames 14, 15 which define printing unit towers T1, T2, T3  
3 and T4. Each of the first three printing units 22, 24 and 26 have  
4 a transfer cylinder 38 disposed to withdraw the freshly printed  
5 sheets from the adjacent impression cylinder and transfer the  
6 freshly printed sheets to the next printing unit via an inter-  
7 station transfer cylinder 40. The last printing unit 28 is shown  
8 equipped with a delivery cylinder 42 which supports the printed  
9 sheet 18 as it is transferred from the last impression cylinder 36  
10 to a delivery conveyor system, generally designated 44, to the  
11 sheet delivery stacker 20.

12 The delivery conveyor system 44 as shown in FIGURE 2 is  
13 of conventional design and includes a pair of endless delivery  
14 gripper chains 46, only one of which is shown carrying at regular  
15 spaced locations along the chains, laterally disposed gripper bars  
16 having gripper fingers used to grip the leading edge of a freshly  
17 printed sheet 18 after it leaves the nip between the delivery  
18 cylinder 42 and impression cylinder 36 of the last printing unit  
19 28. As the leading edge is gripped by the grippers, the delivery  
20 chains 46 pull the sheet away from the impression cylinder 36 and  
21 convey the freshly printed sheet to the sheet delivery stacker 20.

22 Prior to reaching the delivery sheet stacker, the  
23 freshly printed and/or coated sheets 8 pass under a delivery dryer  
24 48 which includes a combination of infra-red thermal radiation,  
25 high velocity hot air flow and a high performance heat and  
26 moisture extractor for drying the ink and/or the protec-  
27 tive/decorative coating.

28 In the exemplary embodiment shown in FIGURE 1, the first  
29 printing unit 22 is equipped with a flexographic printing plate,  
30 and does not require an inking roller train or a dampening system.  
31 If an ink roller train is mounted on the first printing unit, the  
32 form rollers are retracted and locked off when the printing unit  
33 goes on impression. Flexographic aqueous ink is supplied by the  
34 inking/coating unit 110. The remaining printing units 24, 26 and  
35 28 are equipped for lithographic printing and include an inking



00315796-051101

1 apparatus 50 having an inking roller train 52 arranged to transfer  
2 ink from an ink fountain 54 to the plate cylinder 32. This is  
3 accomplished with the aid of a fountain roller 56 and a ductor  
4 roller. The fountain roller 56 projects into the ink fountain 54,  
5 whereupon its surface is wetted with ink. The printing ink Q is  
6 transferred intermittently to the inking roller train 52 by the  
7 ductor roller. The inking roller train 52 supplies ink Q to the  
8 image area of a printing plate P mounted on the plate cylinder 32.

9 The printing ink Q is transferred from the printing  
10 plate P to an ink receptive blanket B which is mounted on the  
11 blanket cylinder 34. The inked image carried on the blanket B is  
12 transferred to a sheet S as the sheet is transferred through the  
13 nip between the impression cylinder 36 and the blanket B.

14 The inking roller arrangement 52 illustrated in FIGURE  
15 1 is exemplary for use in combination with lithographic ink  
16 printing plates. It will be understood that dampening rollers  
17 (not illustrated) will be in direct engagement with the litho-  
18 graphic plate P, but are not used in combination with the  
19 flexographic plate of printing unit 22.

20 Referring now to FIGURE 4, FIGURE 5 and FIGURE 6, the  
21 in-line inking/coating apparatus 10 includes a carriage assembly  
22 58 which supports an applicator head 60. The applicator head 60  
23 includes a hydraulic motor 62, a lower gear train 64, an upper  
24 gear train 65, an applicator roller 66 and a doctor blade assembly  
25 68. The external peripheral surface of the applicator roller 66  
26 is inserted into wetting contact with liquid coating material or  
27 ink contained in a reservoir 70. The reservoir is continuously  
28 supplied with ink or coating which is circulated through the  
29 reservoir 70 from an off-press source by a pump (not illustrated).  
30 The hydraulic motor 62 drives the applicator roller 66 synchro-  
31 nously with the plate cylinder 32 and the blanket cylinder 34 in  
32 response to an RPM control signal from the press drive (not  
33 illustrated) and a feedback signal developed by a tachometer 72.  
34 While a hydraulic drive motor is preferred, an electric drive  
35 motor can be used.

05315796 054101

1           The fluid metering applicator 66 is preferably an anilox  
2 roller which transfers measured amounts of printing ink or coating  
3 material onto the printing plate or blanket. The surface of an  
4 anilox roller is engraved with an array of closely spaced, shallow  
5 depressions referred to as "cells". Ink or coating from the  
6 reservoir 70 flows into the cells as the anilox roller turns  
7 through the reservoir. The transfer surface of the anilox roller  
8 is scraped with a doctor blade 73 to remove excess ink or coating.  
9 The ink or coating remaining on the anilox roller is that  
10 contained within the cells.

11           The anilox roller 66 is cylindrical and may be con-  
12 structed in various diameters and lengths, containing cells of  
13 various sizes and shapes. The volumetric capacity of an anilox  
14 roller is established during manufacturing and is dependent upon  
15 the selection of cell size, shape and number of cells per unit  
16 area. Depending upon the intended application, the cell pattern  
17 may be fine (many small cells per square inch) or coarse (fewer  
18 larger cells per square inch).

19           By applying the ink or coating through the inking/coat-  
20 ing applicator 60, more ink or coating can be delivered to the  
21 sheet 8 as compared with the inking roller train of a lithographic  
22 printing unit. Moreover, color intensity is stronger and more  
23 brilliant because the flexographic ink is applied at a much larger  
24 film thickness than can be applied by the lithographic process and  
25 is not diluted by dampening solution.

26           Preferably, the doctor blade assembly 68 is constructed  
27 as described in U.S. Patent 5,176,077 (DeMoore), which is  
28 incorporated herein by reference.

29           The applicator head 60 includes side frame members 74,  
30 76 which support the applicator roller 66, gear train 64, gear  
31 train 65, doctor blade assembly 68 and the drive motor 62. The  
32 applicator roller 66 is supported at opposite ends on a lower  
33 cradle formed by a pair of end plates 78, 80 which hold the  
34 applicator roller 66 in parallel alignment with the blanket  
35 cylinder 34 (FIGURE 5). The side frame 74, 76 are also provided

00315796 054104

1 with an upper cradle formed by a pair of side plates 82, 84 which  
2 are vertically spaced with respect to the lower side plates 78,  
3 80. Each cradle has a pair of sockets 79, 81 and 83, 85,  
4 respectively, for holding an applicator roller 66 for spot coating  
5 or inking engagement against the plate P of the plate cylinder 32  
6 (FIGURE 4) or the blanket B of the blanket cylinder 34.

7 Preferably, the applicator roller 66 for the upper  
8 cradle (plate) position is an anilox roller having a resilient  
9 transfer surface. In the dual cradle arrangement, the press  
10 operator can quickly change over from blanket inking/coating and  
11 plate inking/coating with minimum press down time, since it is  
12 only necessary to remove and reposition or replace the applicator  
13 roller 66, and wash-up the doctor blade assembly if changing from  
14 ink to coating or vice versa. The capability to selectively  
15 operate in either the flexographic mode or the lithographic mode  
16 and to print or coat from either the plate or blanket position is  
17 referred to herein as the "LITHOFLEX" principle.

18 According to an important feature of the present  
19 invention, the applicator head 60 is supported by the carriage  
20 assembly 58 in a cantilevered, pivotal arrangement which allows  
21 the dual cradle inking/coating apparatus 10 and single cradle  
22 inking/coating apparatus 110 to be installed and used between any  
23 two adjacent printing units, as well as installed on the first and  
24 last printing units of the press. This is made possible by a pair  
25 of cantilevered support arms 88, 90 which are pivotally coupled to  
26 the side plates 74, 76, respectively, on a pivot shaft 77. Each  
27 support arm has a hub portion 88A, 90A, respectively and an  
28 elongated shank portion 88B, 90B, respectively. The elongated  
29 shank portion extends transversely with respect to the shank  
30 portion, and preferably extend perpendicularly with respect to  
31 each other.

32 The cantilevered support arms are pivotally mounted on  
33 the printing tower by pivot blocks 92, 94, respectively. The hub  
34 portions 88A, 90A are journaled for rotation on pivot shafts 96,  
35 98, respectively. The pivot blocks 92, 94 are securely fastened

0915706-051404

1 to the tower 14D, so that the carriage assembly 86 is pivotally  
2 suspended from the pivot shafts 96, 98 in a cantilevered Ferris  
3 support arrangement. The shank portions 88B, 90B are pivotally  
4 coupled to the pivot shaft 77, so that the carriage assembly 58  
5 and the applicator head 60 are capable of independent rotation  
6 with respect to each and with respect to the pivot shaft 77. By  
7 this arrangement, the applicator head 60 is pivotally suspended  
8 from the pivot shaft 77, and remains in an upright orientation as  
9 the support arms rotate from the operative position to the fully  
10 retracted position and vice versa.

11 Thus, the cradles 78, 80 and 82, 84 position the  
12 applicator roller 66 in vertical and horizontal alignment with the  
13 plate cylinder or blanket cylinder when the applicator head is  
14 extended to the operative position. Moreover, because of the  
15 transverse relationship between the hub portion and shank portion  
16 of the support arms, the applicator head 60 and carriage assembly  
17 58 are capable of rotating through a Ferris arc without touching  
18 the adjacent tower. This makes it possible to install the  
19 inking/coating apparatus 10 on any intermediate printing unit  
20 tower (T2, T3), and as well as the first printing unit tower T1  
21 and the last printing unit tower T4. Additionally, because of the  
22 transverse relationship of the support arm hub portion and shank  
23 portion, the lateral projection of the applicator head 60 into the  
24 interstation space between printing units is minimized, thus  
25 assuring virtually unrestricted operator access in the inter-  
26 station space between adjacent printing units when the applicator  
27 head is engaged in the operative position, and completely  
28 unrestricted access when the applicator head is completely  
29 retracted.

30 As shown in FIGURE 1 and FIGURE 2, rotation of the  
31 carriage assembly 58 is counterclockwise from the retracted  
32 position (shown in phantom) to the operative position. The  
33 carriage assembly can be adapted for clockwise rotation from the  
34 retracted position to the operative position for engagement of the  
35 applicator roller to either the plate cylinder or the blanket

00345796 051101

1 cylinder on the dampener side of the tower, assuming that access  
2 to the plate and blanket is not restricted by dampener rollers or  
3 the like.

4 Rotational movement of the support arms 88, 90 is  
5 assisted by counterweights 100, 102 which are secured to the  
6 support arms, respectively, for concurrent rotation with respect  
7 to the pivot blocks 92, 94. With the passive assistance of the  
8 counterweights, the press operator can easily move the ink-  
9 ing/coating assembly 10 from the engaged operative position as  
10 shown in FIGURE 4 to the fully retracted idle position as shown in  
11 phantom in FIGURE 1. Preferably, rotation of the carriage  
12 assembly 58 is assisted by power means such as a torsion spring,  
13 electric motor, or hydraulic motor.

14 The inking/coating apparatus 10 is releasably locked  
15 into the engaged position as shown in FIGURE 4 by releasable latch  
16 couplings 103, 105 which secure the support arms 88, 90 to the  
17 press side frames 14, 15, respectively, of the printing unit tower  
18 T4 in the operative position. Coating engagement of the applica-  
19 tor roller 66 against the blanket cylinder 34 is produced by power  
20 actuators, preferably pneumatic cylinders 104, 106 which have  
21 extendable/retractable power transfer arms 104A, 106A, respective-  
22 ly. The pneumatic cylinder 104 is pivotally coupled to the  
23 support arm 88 by a pivot linkage 108, and the second pneumatic  
24 cylinder 106 is pivotally coupled to the support arm 90 by a pivot  
25 linkage 109. In response to actuation of the pneumatic cylinders  
26 104, 106, the power transfer arms are retracted. As the arms  
27 retract, the inking/coating head 60 is rotated counterclockwise on  
28 the pivot shaft 77, thus moving the applicator roller 66 into  
29 coating engagement with the blanket cylinder 34.

30 The pivot linkage 108 includes a bell crank 111 which is  
31 mounted for pivotal movement on a pin 113. The pin 113 is  
32 supported by a clevis plate 115 which is attached to the support  
33 arm 88. One end of the bell crank is pivotally coupled to the  
34 actuator arm 104A, and a cam roller 117 is mounted for rotation on  
35 its opposite end.

09315706-054404

1 The cam roller 117 is engagable against an adjustable  
2 stop 119 which is rigidly secured to the side plate 74. Counter-  
3 clockwise shifting of the handle H moves a cam follower 121 into  
4 a latch pocket 123 of a receiver block 125 as the cam roller 117  
5 is moved into engagement with the adjustable stop 119 in the  
6 interlocked, operative position. Referring to FIGURE 4, FIGURE 5  
7 and FIGURE 6, the receiver block is rigidly secured to the  
8 delivery side face of the printing unit tower by machine screws.

9 When the plate P goes on impression, power is applied to  
10 the pneumatic actuator 104 and the power transfer arm 104A  
11 retracts, thus causing the bell crank 111 to rotate counterclock-  
12 wise about the pin 113. The torque applied by the actuator is  
13 transmitted to the applicator head 60 through the cam roller 117  
14 and the adjustable stop 119. Counterclockwise movement of the  
15 applicator head 60 relative to the support shaft 77 carries the  
16 applicator roller 66 into engagement with the plate P.

17 The adjustable stop 119 has a threaded bolt 119A which  
18 is engagable with the cam roller 117. The striking point of  
19 engagement is preset so that the applicator roller 66 is properly  
20 positioned for engagement with the plate P or blanket B when the  
21 applicator head 60 is interlocked with the press frame 14 and the  
22 printing unit goes on impression.

23 Referring to FIGURE 5, an inking/coating apparatus 110  
24 having a single head is illustrated. The construction of this  
25 alternative embodiment is identical in all respects with the dual  
26 head arrangement, with the exception that only a single gear train  
27 and a single cradle for holding the applicator roller is provided.  
28 In both embodiments, the inking/coating head 60 remains upright as  
29 it swings through an arc, similar to the movement of a Ferris  
30 wheel. Because of the upright orientation of the inking/coating  
31 head 60 as it moves between the extended and retracted positions,  
32 the usual platform spacing between printing unit towers provides  
33 adequate clearance to permit extension and retraction of the  
34 carriage assembly 58 without interference with operator access to  
35 the printing units. This is a significant advantage in that it

0935796-054494

1 permits the in-line inking/coating apparatus to operate effective-  
2 ly in the interstation space between any adjacent printing units,  
3 and without blocking or obstructing access to the cylinders of the  
4 printing units when the inking/coating apparatus is in the fully  
5 retracted position as indicated in FIGURE 1.

6 Moreover, when the in-line inking/coating apparatus is  
7 in the fully retracted position, the applicator roller 66 is  
8 conveniently positioned on the dampener side of the printing unit  
9 for inspection, clean-up or removal. Additionally, the doctor  
10 blade assembly is also conveniently positioned for inspection,  
11 removal, adjustment or clean-up. The doctor blade reservoir and  
12 coating circulation lines can also be cleaned while the printing  
13 unit is running as well as when the press has been stopped for  
14 change-over from one type of ink or coating to another.

15 When the inking/coating apparatus is used for applying  
16 an aqueous ink or an aqueous coating material, the water component  
17 on the freshly printed sheet S is evaporated by a high velocity,  
18 hot air interstation dryer and high volume heat and moisture  
19 extractor units 112 and 114, as shown in FIGURE 1, FIGURE 4 and  
20 FIGURE 5. The dryer/extractor units 112 and 114 are oriented to  
21 direct high velocity heated air onto the freshly printed/coated  
22 sheet as it is transferred by the impression cylinder 36 and the  
23 intermediate transfer cylinder 40. By this arrangement, the  
24 freshly printed aqueous ink or coating is completely dry before  
25 the sheet is overprinted in the next printing unit.

26 The high velocity, hot air dryer and high performance  
27 heat and moisture extractor units 112, 114 utilize high velocity  
28 air jets which scrub and break-up the moist air level which clings  
29 to the surface of each freshly printed sheet. Within each dryer,  
30 high velocity air is heated to a high temperature as it flows  
31 across a resistance heating element within an air delivery baffle  
32 tube. High velocity jets of hot air are discharged through  
33 multiple airflow apertures through an exposure zone Z (FIGURE 4  
34 and FIGURE 5) onto the freshly printed/coated sheet S as it is  
35 transferred by the impression cylinder 36 and transfer cylinder

00315796-0541001

40, respectively. Each dryer assembly includes a pair of air delivery dryer heads which are arranged in spaced, side-by-side relation. The high velocity, hot air dryer and high performance heat and moisture extractor units 112, 114 are preferably constructed as disclosed in co-pending U.S. Patent Application Serial No. 08/132,584, filed October 6, 1993, entitled "High Velocity Hot Air Dryer", assigned to the assignee of the present invention and which is incorporated herein by reference.

The high velocity, hot moisture-laden air displaced from each printed sheet is extracted from the dryer exposure zone Z and completely exhausted from the printing unit by the high volume extractors. Each extractor head includes a manifold coupled to the dryer heads and draws the moisture, volatiles and high velocity hot air through a longitudinal gap between the dryer heads. According to this arrangement, each printed sheet is dried before it is run through the next printing unit.

The water-based inks used in flexographic printing dry at a relatively moderate drying temperature provided by the interstation high velocity hot air dryers/extractors 112, 114. Because each freshly printed sheet is dried between each printing unit, clarity and print quality are substantially improved since the aqueous ink is dried at each printing unit before it enters the next printing unit. Since the aqueous ink is dry before the sheet enters the next printing unit, back-trapping on the blanket of the next printing unit is completely eliminated. This interstation drying arrangement makes it possible to print aqueous inks such as metallic ink and opaque white ink at one printing unit, and then overprint at the next printing unit.

Moreover, this arrangement permits the first printing unit to be used as a coater in which an aqueous coating is applied to low grade paper such as recycled paper to trap and seal in lint, dust, spray powder and other debris and provide a smoother, durable surface which is overprinted in the next printing unit. An UV-curable coating can be applied over the first down overprinted (aqueous) coating in the last printing unit. The first



00315796 051101  
TOTED 06/21/60

1 down layer seals the surface of the low grade, rough substrate and  
2 improves overprinted dot definition while preventing strike-  
3 through and show-through.

4 Preferably, the applicator roller 66 is either metal or  
5 ceramic when it is used for applying a coating material to the  
6 blanket B on the cylinder 34. When the applicator roller 66 is  
7 applied to the plate, it is preferably constructed as an anilox  
8 roller having a resilient transfer surface for engaging a  
9 flexographic printing plate. Suitable resilient roller surface  
10 materials include Buna N synthetic rubber and EPDM (terpolymer  
11 elastomer).

12 It will be appreciated that the inking/coating apparatus  
13 10 is capable of applying a wide range of ink types, including  
14 fluorescent (Day Glo), pearlescent, metallics (gold, silver and  
15 other metallics), glitter, scratch and sniff (micro-encapsulated  
16 fragrance), scratch and reveal, luminous, pressure-sensitive  
17 adhesives and the like.

18 The press operator can eliminate the dampener roller  
19 assembly altogether, and the inking/coating apparatus 10 can  
20 selectively apply aqueous inks and coatings to a flexographic or  
21 waterless printing plate and the blanket. Moreover, overprinting  
22 of the aqueous inks and coatings can be carried out in the next  
23 printing unit since the aqueous inks and coatings are completely  
24 dried by the high velocity, hot air interstation dryer and high  
25 volume heat and moisture extractor assembly of the present  
26 invention.

27 The aqueous inks and coatings as used in the present  
28 invention contain colored pigments and/or soluble dyes, binders  
29 which fix the pigments onto the surface of the printed sheet and  
30 waxes, defoamers and thickeners. Aqueous printing inks predomi-  
31 nantly contain water as a solvent, diluent and/or vehicle. The  
32 thickeners which are preferred include algonates, starch,  
33 cellulose and its derivatives, for example cellulose esters or  
34 cellulose ethers and the like. Coloring agents including organic  
35 as well as inorganic pigments may be derived from dyes which are

0015796 054404

1 insoluble in water. Also, the printing ink may contain water and  
2 may be predominantly glycol or the like, with the pigment being  
3 bound by an appropriate resin. When metallic inks are printed,  
4 the cells of the anilox roller must be appropriately sized to  
5 prevent the metal particles from getting stuck within the cells.  
6 The cell size is critical, and for metallic gold ink, the anilox  
7 roller should have a screen line count in the range of 175-300  
8 lines per inch.

9 The inking/coating apparatus 10 can also apply UV-  
10 curable inks and coatings. If UV-curable inks and coatings are  
11 utilized, ultra-violet dryers/extractors are installed adjacent  
12 the high velocity hot air dryer/extractor units 112, 114,  
13 respectively.

14 Moreover, by utilizing the coating apparatus on the  
15 first printing unit, a seal coating can be applied to trap lint,  
16 spray powder, dust and other debris, and cover defects on lower  
17 grade paper which will improve print quality, which can then be  
18 overprinted on the next in-line printing unit.

19 It will be appreciated that the "LITHOFLEX" system  
20 described herein makes it possible to selectively operate a  
21 printing unit in either the flexographic printing mode or the  
22 lithographic printing mode, while also providing the capability to  
23 print or coat from either the plate or blanket position. The dual  
24 cradle support arrangement of the present invention makes it  
25 possible to quickly change over from inking/coating at the blanket  
26 cylinder position to inking/coating at the plate cylinder position  
27 with minimum press down-time, since it is only necessary to remove  
28 and reposition or replace the applicator roller 66 while the  
29 printing/inking apparatus is in the retracted position.

30 Moreover, the press operator may elect to spot or  
31 overall coat with aqueous ink/coating from the plate for one job,  
32 and then spot and/or overall coat from the blanket during the next  
33 job. Since the doctor blade assembly can be flushed and washed-up  
34 quickly and the applicator roller can be changed out quickly, it  
35 is possible to spot coat or overall coat from the plate position

0034576 054101

1 or the blanket position with aqueous inks or coatings during the  
2 first press run and then spot coat or overall coat with UV-curable  
3 inks or coatings from the plate position or from the blanket  
4 position during the next press run. The inking/coating apparatus  
5 is completely out of the way in the retracted position; conse-  
6 quently, the doctor blade reservoir and supply lines may be  
7 flushed and washed-up by automatic wash-up equipment while the  
8 printing unit is printing another job.

9 The positioning of the applicator head and roller  
10 assembly relative to the plate and blanket is repeatable to a pre-  
11 determined, preset impression position. Consequently, no printing  
12 unit adjustment or alteration is required, except for flushing the  
13 doctor blade assembly and cleaning or replacing the applicator  
14 roller to accommodate a different kind of ink or coating.  
15 Although manual extension and retraction have been described in  
16 connection with the exemplary embodiment, extension to the  
17 operative position and retraction to a non-operative position can  
18 be carried out automatically by hydraulic or electric motor  
19 servomechanisms.

20 The cantilevered, Ferris wheel support arrangement  
21 allows the inking/coating apparatus to operate effectively in the  
22 interstation space between any adjacent printing units, as well as  
23 on the first or last printing units of the press, without blocking  
24 or obstructing the interstation space or restricting operator  
25 access to the cylinders of any of the printing units.

26 Finally, because the inking/coating apparatus of the  
27 present invention is mounted on a printing unit tower and is  
28 extendable to the operative position without requiring adjustment  
29 or alteration of the printing unit cylinders, it can be used for  
30 applying ink or coating to the blanket cylinder of a rotary offset  
31 web press, or to the blanket of a dedicated coating unit.

32 Although the present invention and its advantages have  
33 been described in detail, it should be understood that various  
34 changes, substitutions and alterations may be made herein without

- 1 departing from the spirit and scope of the present invention as
- 2 defined by the appended claims.

09315796 054101

What is claimed is:

1           1. In a printing press of the type having side frame  
2 members forming a printing unit tower on which a plate cylinder  
3 and blanket cylinder are supported for rotation, the improvement  
4 comprising:

5                 inking/coating apparatus for applying ink or  
6 coating material to a plate mounted on the plate cylinder or to a  
7 blanket mounted on the blanket cylinder when the inking/coating  
8 apparatus is in an operative position; and,

9                 a carriage assembly including a support arm having  
10 a first end portion pivotally coupled to the printing unit tower  
11 and a second end portion pivotally coupled to the inking/coating  
12 apparatus, the carriage assembly being movable to an operative  
13 position in which the inking/coating apparatus is suspended  
14 laterally adjacent to the plate and blanket cylinders, and being  
15 movable to a retracted position in which the inking/coating  
16 apparatus is elevated with respect to the plate and blanket  
17 cylinders.

1           2. The invention as set forth in claim 1, wherein the  
2 inking/coating apparatus comprises:

3                 a doctor blade assembly having a reservoir for  
4 receiving ink or liquid coating material;

5                 an applicator roller coupled to the doctor blade  
6 assembly in fluid communication with the reservoir, the applicator  
7 roller being engagable with a printing plate on the plate cylinder  
8 or with a blanket on the blanket cylinder when the inking/coating  
9 apparatus is in the operative position.

1           3. The invention as set forth in claim 2, the  
2 applicator roller comprising:

3                 an anilox roller having a resilient transfer  
4 surface.

4. The invention as set forth in claim 1, including a counterweight coupled to the support arm.

1 5. The invention as set forth in claim 1, further  
2 comprising:

3 a power actuator pivotally coupled to the support  
4 arm, the power actuator having a power transfer arm which is  
5 extendable and retractable; and,

6 apparatus coupled to the power transfer arm for  
7 converting extension or retraction movement of the power transfer  
8 arm into pivotal movement of the inking/coating apparatus relative  
9 to the support arm.

1 6. The invention as set forth in claim 5, in which the  
2 movement converting apparatus comprises:

3 a bell crank plate having a first end portion  
4 coupled to the power transfer arm and having a second end portion  
5 for engaging a stop member;

6 a stop member secured to the inking/coating  
7 apparatus; and,

8 a clevis plate secured to the support arm and  
9 pivotally coupled to the bell crank plate.

1 7. The invention as set forth in claim 1, the  
2 inking/coating apparatus comprising:

3 an applicator head having first and second side  
4 frame members pivotally coupled to the carriage assembly;

5 a doctor blade assembly mounted between the first  
6 and second side frame members, the doctor blade assembly including  
7 a reservoir for receiving ink or liquid coating material;

8 cradle means mounted on the first and second side  
9 frame members, respectively;

10 an applicator roller mounted for rotation on the  
11 cradle means and coupled to the doctor blade assembly for rolling  
12 contact with ink or coating material in the reservoir, the

00315796-054101  
TOP SECRET

13 applicator roller being engagable with a printing plate on the  
14 plate cylinder or with a blanket on the blanket cylinder in the  
15 operative position; and,  
16 motor means coupled to the applicator roller for  
17 rotating the applicator roller.

1 8. The invention as set forth in claim 7,  
2 the cradle means including first and second sockets  
3 disposed on the first and second side frame members respectively;  
4 and,  
5 the applicator roller being mounted for rotation on  
6 the first and second sockets.

1 9. The invention as set forth in claim 7,  
2 the cradle means including first and second sockets  
3 disposed on the first and second side frame members, respectively,  
4 and third and fourth sockets disposed on the first and second side  
5 frame members, respectively;  
6 the applicator roller being mountable for rotation  
7 on the first and second sockets for applying ink or coating  
8 material to the plate when the carriage assembly is in the  
9 operative position; and,  
10 the applicator roller being mountable for rotation  
11 on the third and fourth sockets for applying ink or coating  
12 material to the blanket when the carriage assembly is in the  
13 operative position.

1 10. The invention as set forth in claim 1, comprising:  
2 male and female latch coupling members mounted on  
3 the carriage assembly and on the printing unit tower, respective-  
4 ly, for releasably latching the carriage assembly in interlocking  
5 engagement with the printing unit tower in the operative position.

1 11. The invention as set forth in claim 1, wherein the  
2 support arm comprises an elongated shank portion and a hub portion

00315796 054104  
TOP SECRET

3 which extends transversely with respect to the shank portion, the  
4 elongated shank portion being pivotally coupled to the ink-  
5 ing/coating apparatus and the hub portion being pivotally coupled  
6 to the printing unit tower.

1 12. A sheet-fed, rotary offset printing press compris-  
2 ing, in combination:

3 at least one printing unit or dedicated coating  
4 unit having side frame members forming a tower;

5 at least one cylinder mounted for rotation on the  
6 tower for printing ink or coating material onto sheets passing  
7 through the printing unit or dedicated coating unit;

8 inking/coating apparatus including a doctor blade  
9 assembly having a reservoir for holding ink or coating liquid, a  
10 rotatable applicator roller and means for applying ink or coating  
11 liquid from the reservoir onto a peripheral surface portion of the  
12 applicator roller; and,

13 support apparatus mounted on the printing unit  
14 tower for pivotal movement, said support apparatus being movably  
15 coupled to the inking/coating apparatus for supporting the  
16 inking/coating apparatus for movement to an operative position in  
17 which the applicator roller is engagable with a plate or a blanket  
18 on the cylinder, and for movement to a retracted position in which  
19 the inking/coating apparatus is supported at an elevated position  
20 above the cylinder.

1 13. A rotary offset printing press comprising, in  
2 combination:

3 a plate cylinder having a printing plate mounted  
4 thereon;

5 a blanket cylinder having an ink receptive blanket  
6 disposed in ink transfer engagement with the plate cylinder for  
7 transferring ink from the image surface areas of the printing  
8 plate to the ink receptive blanket;



00345796 051101  
TOP SECRET

9 an impression cylinder disposed adjacent the  
10 blanket cylinder thereby defining a nip between the impression  
11 cylinder and the blanket whereby the printing ink is transferred  
12 from the blanket to a substrate as the substrate is transferred  
13 through the nip;

14 inking/coating apparatus for applying ink or  
15 coating material to the plate or to the blanket;

16 support apparatus mounted on the printing press for  
17 pivotal movement, said support apparatus being movably coupled to  
18 the coating apparatus for supporting the inking/coating apparatus  
19 for movement to an operative position in which the inking/coating  
20 apparatus is engagable with the plate or the blanket, and for  
21 movement to a retracted position in which the inking/coating  
22 apparatus is supported at an elevated position above the press;  
23 and,

24 a dryer mounted on the press for discharging heated  
25 air on the freshly printed substrate.

1 14. A rotary offset printing press as defined in claim  
2 13, wherein:

3 the dryer is mounted adjacent the impression  
4 cylinder for discharging heated air onto a freshly printed  
5 substrate while the substrate is in contact with the impression  
6 cylinder.

1 15. A rotary offset printing press as defined in claim  
2 13, comprising:

3 an extractor coupled to the dryer for extracting  
4 hot air, moisture and volatiles from an exposure zone between the  
5 dryer and the freshly printed substrate.

1 16. A rotary offset printing press as defined in claim  
2 13, comprising:

09315796 154104  
TOP SECRET

3 a transfer cylinder disposed in an interstation  
4 position on the press and coupled in sheet transfer relation with  
5 the impression cylinder; and,  
6 an interstation dryer disposed adjacent the  
7 transfer cylinder for discharging heated air onto a freshly  
8 printed or coated substrate after it has been transferred from the  
9 impression cylinder and while it is in contact with the inter-  
10 mediate transfer cylinder.

1 17. In a printing press of the type having side frame  
2 members forming a tower on which a blanket cylinder is supported  
3 for rotation, the improvement comprising:

4 inking/coating apparatus for applying ink or  
5 coating material to a blanket mounted on the blanket cylinder when  
6 the inking/coating apparatus is in an operative position; and,

7 a carriage assembly movably coupled to the tower  
8 and to the inking/coating apparatus for producing Ferris wheel  
9 movement of the inking/coating apparatus to the operative position  
10 in which the inking/coating apparatus is suspended laterally  
11 adjacent to the blanket cylinder, and to a retracted position in  
12 which the inking/coating apparatus is elevated with respect to the  
13 blanket cylinder.

1 18. The invention as set forth in claim 17, wherein the  
2 tower includes a plate cylinder and a plate mounted on the plate  
3 cylinder, the inking/coating apparatus including:

4 first cradle means for supporting an applicator  
5 roller for engagement against the plate when the inking/coating  
6 apparatus is in the operative position; and,

7 second cradle means for supporting an applicator  
8 roller for engagement against the blanket when the inking/coating  
9 apparatus is in the operative position.

00315706 051101  
TOP SECRET

1 19. The invention as set forth in claim 17, comprising:  
2 said carriage assembly including a support arm  
3 having a first end portion pivotally coupled to the tower and  
4 having a second end portion;  
5 a common pivot shaft on which the support arm  
6 second end portion and the inking/coating apparatus are pivotally  
7 mounted; and,  
8 male and female latch members coupled between the  
9 common pivot shaft and the tower, with one of the latch members  
10 being secured to the common pivot shaft and the other latch member  
11 being secured to the tower, the latch members being mateable in  
12 interlocking engagement when the inking/coating apparatus is in  
13 the operative position.

1 20. The invention as set forth in claim 17, further  
2 comprising:  
3 a power actuator pivotally coupled to the support  
4 arm, the power actuator having a power transfer arm which is  
5 extendable and retractable; and,  
6 apparatus coupled to the power transfer arm for  
7 converting extension or retraction movement of the power transfer  
8 arm into pivotal movement of the inking/coating apparatus relative  
9 to the common pivot shaft.

1 21. The invention as set forth in claim 20, in which  
2 the movement converting apparatus comprises:  
3 a bell crank plate having a first end portion  
4 coupled to the power transfer arm and having a second end portion  
5 for engaging a stop member;  
6 a stop member secured to the inking/coating  
7 apparatus; and,  
8 a clevis plate secured to the support arm and  
9 pivotally coupled to the bell crank plate.

00315796-054104

1 22. The invention as set forth in claim 1, wherein the  
2 inking/coating apparatus comprises:  
3 an applicator roller having a resilient transfer  
4 surface.

1 23. The invention as set forth in claim 1, wherein the  
2 applicator roller is mounted for engagement to a plate in the  
3 plate cylinder position, the applicator roller comprising an  
4 anilox roller having a resilient transfer surface.

1 24. A method for rotary offset printing in a rotary  
2 offset press of the type including first and second printing  
3 units, and using aqueous or UV-curable printing ink or coating  
4 material in the operation of at least the first printing unit,  
5 comprising the following steps performed at each printing unit in  
6 succession:

7 spot or overall coating with aqueous ink/aqueous  
8 coating or UV-curable ink/UV-curable coating from the plate;

9 spot and/or overall coating the blanket with  
10 aqueous ink/aqueous coating or UV-curable ink or UV-curable  
11 coating from the blanket;

12 transferring the printing ink or coating from the  
13 printing plate to the blanket;

14 transferring the printed image from the blanket to  
15 a substrate as the substrate is transferred through the nip  
16 between an impression cylinder and the blanket; and,

17 drying the ink or coating on the freshly printed  
18 substrate before the substrate is processed in the second printing  
19 unit.

1 25. A method for rotary offset printing as defined in  
2 claim 24,

3 wherein the drying step is performed by discharging  
4 hot air onto the freshly printed/coated substrate after it has  
5 been transferred from the first printing unit and while it is

00315796 051101  
FOT59 26251220

6 contact with an intermediate transfer cylinder, but before it is  
7 processed in the second printing unit.

1 26. A method for rotary offset printing as defined in  
2 claim 24,

3 wherein the drying step is performed by directing  
4 high velocity, heated air onto the freshly printed/coated  
5 substrate while the freshly printed/coated substrate is in contact  
6 with an impression cylinder.

1 27. A method for rotary offset printing as defined in  
2 claim 24, including the steps:

3 transferring the freshly printed substrate to an  
4 intermediate transfer cylinder; and,

5 drying the freshly printed substrate while it is in  
6 contact with the intermediate transfer cylinder.

1 28. A method for rotary offset printing as defined in  
2 claim 24, including the step:

3 extracting hot air, moisture and volatiles from an  
4 exposure zone above the freshly printed/coated substrate while the  
5 freshly printed/coated substrate is in contact with the impression  
6 cylinder.

1 29. A method for rotary offset printing as defined in  
2 claim 24, including the steps:

3 applying a primer coating of an aqueous coating  
4 material or UV-curable coating material to a substrate in the  
5 first printing unit;

6 trapping and sealing dust, lint, spray powder and  
7 other debris under the primer coating; and,

8 drying the primer coating on the substrate before  
9 the substrate is overprinted in the second printing unit.

00315796 051101

1 30. A method for rotary offset printing in a rotary  
2 offset press of the type including first and second printing  
3 units, and using aqueous or UV-curable printing ink/coating  
4 material in the operation of at least the first printing unit  
5 comprising the following steps performed at each printing unit in  
6 succession:

7 transferring the printing ink/coating material to  
8 a printing plate at the first printing unit;

9 transferring the printing ink/coating material from  
10 the printing plate to a blanket;

11 transferring the printed image from the blanket to  
12 a substrate as the substrate is transferred through the nip  
13 between an impression cylinder and the blanket; and,

14 drying the printing ink on the freshly printed  
15 substrate before the substrate is processed in the second printing  
16 unit.

1 31. A method for rotary offset printing as defined in  
2 claim 30,

3 wherein the drying step is performed by discharging  
4 hot air onto the freshly printed substrate after it has been  
5 transferred from the first printing unit and while it is in  
6 contact with an intermediate transfer cylinder, but before it is  
7 processed in the second printing unit.

1 32. A method for rotary offset printing as defined in  
2 claim 30, wherein the drying step is performed by directing high  
3 velocity, heated air onto the freshly printed substrate while the  
4 freshly printed substrate is in contact with the impression  
5 cylinder.

1 33. A method for rotary offset printing as defined in  
2 claim 30, including the steps:

3 transferring the freshly printed substrate to an  
4 intermediate transfer cylinder; and,

5                   drying the freshly printed substrate while it is in  
6                   contact with the intermediate transfer cylinder.

1                   34. A method for rotary offset printing as defined in  
2                   claim 30, including the step:

3                   extracting hot air, moisture and volatiles from an  
4                   exposure zone above the substrate while the substrate is in  
5                   contact with the impression cylinder.

00315796-051101

"RETRACTABLE INKING/COATING APPARATUS  
HAVING FERRIS MOVEMENT BETWEEN PRINTING UNITS"

Abstract of the Disclosure

1 A retractable in-line inking/coating apparatus selec-  
2 tively applies either spot or overall ink/coating to a blanket or  
3 flexographic plate on a blanket cylinder or spot coating or  
4 overall ink/coating to a flexographic printing plate on a plate  
5 cylinder in a rotary offset printing press. The inking/coating  
6 apparatus is pivotally mounted on the tower of a printing unit or  
7 dedicated coating unit, and is extended into and retracted out of  
8 inking/coating engagement by a carriage assembly which is  
9 pivotally coupled to the printing unit tower. Because of the  
10 pivotal support provided by a cantilevered support arm, the  
11 inking/coating apparatus can be raised and lowered through a  
12 Ferris wheel arc movement between adjacent printing units. The  
13 aqueous component of the printing ink or coating is evaporated by  
14 a high velocity, hot air interstation dryer and a high performance  
15 heat and moisture extractor so that the ink on a freshly printed  
16 sheet is dry before the sheet is printed on the next printing  
17 unit. Thus, flexographic ink or coating applied at the first  
18 printing unit can immediately be overprinted on subsequent  
19 printing units.

\* \* \* \* \*

DTN118750148DOC88813APP

0015716-054101



PATENT

JOINT  
UTILITY

Attorney Docket  
No. B5012

DECLARATION AND POWER OF ATTORNEY

We, RONALD M. RENDLEMAN, HOWARD W. DEMOORE, JOHN W. BIRD, joint inventors herein, hereby declare that:

Our residence, post office address and citizenship are as stated below next to our names.

We believe that we are the original, first and joint inventors of the subject matter which is claimed and for which a patent is sought on the invention entitled

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS",

the specification of which is attached hereto.

We hereby state that we have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to in this declaration.

We each individually acknowledge the duty to disclose to the U.S. Patent Office all information known to me that is material to the patentability of any claim in accordance with Title 37, Code of Federal Regulations, §1.56, and which is material to the examination of this application, namely, information where there is a substantial likelihood that a reasonable examiner would consider it important in deciding whether to allow the application to issue as a patent.

We hereby claim foreign priority benefits under Title 35, United States Code §119 of any foreign application(s) for patent or inventor's certificate listed below and have also identified below any foreign application for patent or inventor's certificate having a filing date before that of the application on which priority is claimed:

<u>Country</u>	<u>Application No.</u>	<u>Filing Date</u> <u>(day, month, year)</u>
----------------	------------------------	---

- NONE -

We hereby claim the benefit under Title 35, United

0015796-051101

States Code §120 of any United States application(s) listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States application in the manner provided by the first paragraph of Title 35, United States Code §112, we acknowledge the duty to disclose material information as defined in Title 37, Code of Federal Regulations §1.56(a) which occurred between the filing date of the prior application and the national or PCT international filing date of this application:

<u>U.S. Serial No.</u>	<u>U.S. Filing Date</u>	<u>Status</u>
------------------------	-------------------------	---------------

- NONE -

We hereby appoint DENNIS T. GRIGGS, Registration No. 27,790, of the firm of AKIN, GUMP, STRAUSS, HAUER & FELD, L.L.P., our attorney to prosecute this application and to transact all business in the U.S. Patent and Trademark Office connected therewith. We request that all correspondence be addressed to:

Dennis T. Griggs  
Akin, Gump, Strauss, Hauer & Feld, L.L.P.  
1700 Pacific Avenue, Suite 4100  
Dallas, Texas 75201-4618

Phone: 214/969-2747

We hereby declare that all statements made herein of our own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of this application or any patent issued thereon.

Full name of first joint Inventor: Ronald M. Rendleman 1-00  
Residence: Dallas, Texas TX  
Citizenship: U.S.  
Post Office Address: 4331 Royal Ridge  
Dallas, Texas 75229

Date: 5/1/95

Ronald M. Rendleman  
-246- →

00315706 051101  
TOTED: 06257600

Full name of  
second joint Inventor: Howard W. DeMoore 200  
Residence: Dallas, Texas  
Citizenship: U.S. TX  
Post Office Address: 10954 Shady Trail  
Dallas, Texas 75220

Date: May 1, 1995 Howard W. DeMoore  
Howard W. DeMoore

Full name of  
third joint Inventor: John W. Bird 300  
Residence: Carrollton, Texas  
Citizenship: U.S. TX  
Post Office Address: 1514 Iroquois Circle  
Carrollton, Texas 75007

Date: May 1, 1995 John W. Bird  
John W. Bird

00315796 164104

B6012

SMALL ENTITY  
INDEPENDENT INVENTOR

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

DECLARATION CLAIMING SMALL ENTITY STATUS  
(37 C.F.R. §1.9(f) and §1.27 (b)) - INDEPENDENT INVENTOR

I, RONALD M. RENDLEMAN, hereby declare that I qualify as an independent inventor as defined in 37 C.F.R. §1.9(c) for the purposes of paying reduced fees under Section 41(a) and (b) of Title 35, United States Code, to the U.S. Patent and Trademark Office with regard to the invention entitled

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS"

X in the application filed herewith.

\_\_\_\_\_ in U.S. application Serial No. \_\_\_\_\_ filed \_\_\_\_\_.

\_\_\_\_\_ patent No. \_\_\_\_\_, issued \_\_\_\_\_.

I have not assigned, granted, conveyed or licensed, and am under no obligation under contract or law to assign, grant, convey or license, any rights in the invention to any person who could not be classified as an independent inventor under 37 C.F.R. §1.9(c) if that person had made the invention, or to any concern which would not qualify as a small business concern under 37 C.F.R. §1.9(d) or a non-profit organization under 37 C.F.R. §1.9(e).

Each person, concern or organization to which I have assigned, granted, conveyed, or licensed or am under any obligation under contract or law to assign, grant, convey, or license any rights in the invention is identified below:

\_\_\_\_\_ no such person, concern or organization exists.

X any such person, concern or organization is identified below, if applicable:

Full Name Howard W. DeMoore

Address 10954 Shady Trail

Dallas, Texas 75220

X individual

small business concern

nonprofit organization

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small entity is no longer appropriate pursuant to 37 C.F.R. §1.28(b).

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

Printed Name of Inventor: Ronald M. Rendleman

Date: 5/1/95

Ronald M. Rendleman  
Signature of Inventor

SMALL ENTITY  
INDEPENDENT INVENTOR

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

DECLARATION CLAIMING SMALL ENTITY STATUS  
(37 C.F.R. §1.9(f) and §1.27 (b)) - INDEPENDENT INVENTOR

I, HOWARD W. DEMOORE, hereby declare that I qualify as an independent inventor as defined in 37 C.F.R. §1.9(c) for the purposes of paying reduced fees under Section 41(a) and (b) of Title 35, United States Code, to the U.S. Patent and Trademark Office with regard to the invention entitled

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS"☒ X in the application filed herewith.

\_\_\_\_\_ in U.S. application Serial No. \_\_\_\_\_ filed \_\_\_\_\_.

\_\_\_\_\_ patent No. \_\_\_\_\_, issued \_\_\_\_\_.

I have not assigned, granted, conveyed or licensed, and am under no obligation under contract or law to assign, grant, convey or license, any rights in the invention to any person who could not be classified as an independent inventor under 37 C.F.R. §1.9(c) if that person had made the invention, or to any concern which would not qualify as a small business concern under 37 C.F.R. §1.9(d) or a non-profit organization under 37 C.F.R. §1.9(e).

Each person, concern or organization to which I have assigned, granted, conveyed, or licensed or am under any obligation under contract or law to assign, grant, convey, or license any rights in the invention is identified below:

\_\_\_\_\_ no such person, concern or organization exists.

☒ X any such person, concern or organization is identified below, if applicable:

Full Name Printing Research, Inc.

Address 10954 Shady Trail

Dallas, Texas 75220

individual ☒ small business concern

nonprofit organization

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small entity is no longer appropriate pursuant to 37 C.F.R. §1.28(b).

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

Printed Name of Inventor: Howard W. DeMoore

Date: May, 1990

Howard W. DeMoore  
Signature of Inventor

00315796 DE4404  
FOI b6 b7C

SMALL ENTITY  
INDEPENDENT INVENTOR

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

DECLARATION CLAIMING SMALL ENTITY STATUS  
(37 C.F.R. §1.9(f) and §1.27 (b)) - INDEPENDENT INVENTOR

I, JOHN W. BIRD, hereby declare that I qualify as an independent inventor as defined in 37 C.F.R. §1.9(c) for the purposes of paying reduced fees under Section 41(a) and (b) of Title 35, United States Code, to the U.S. Patent and Trademark Office with regard to the invention entitled

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS"

X in the application filed herewith.

\_\_\_\_\_ in U.S. application Serial No. \_\_\_\_\_ filed  
\_\_\_\_\_.

\_\_\_\_\_ patent No. \_\_\_\_\_, issued \_\_\_\_\_.

I have not assigned, granted, conveyed or licensed, and am under no obligation under contract or law to assign, grant, convey or license, any rights in the invention to any person who could not be classified as an independent inventor under 37 C.F.R. §1.9(c) if that person had made the invention, or to any concern which would not qualify as a small business concern under 37 C.F.R. §1.9(d) or a non-profit organization under 37 C.F.R. §1.9(e).

Each person, concern or organization to which I have assigned, granted, conveyed, or licensed or am under any obligation under contract or law to assign, grant, convey, or license any rights in the invention is identified below:

\_\_\_\_\_ no such person, concern or organization exists.

X any such person, concern or organization is identified below, if applicable:



Full Name Howard W. DeMoore

Address 10954 Shady Trail

Dallas, Texas 75220

☒ individual ☐ small business concern  
☐ nonprofit organization

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small entity is no longer appropriate pursuant to 37 C.F.R. §1.28(b).

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

Printed Name of Inventor: John W. Bird

Date: May 1, 1995

John W. Bird  
Signature of Inventor

B6012

SMALL ENTITY  
SMALL BUSINESS CONCERN

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

VERIFIED STATEMENT (DECLARATION) CLAIMING SMALL  
ENTITY STATUS (37 C.F.R. §1.9(f) and §1.27(c))--  
SMALL BUSINESS CONCERNI, HOWARD W. DEMOORE

hereby declare that I am

- ☐ the owner of the small business concern identified below:
- ☒ an official of the small business concern empowered to act on behalf of the concern identified below:

NAME OF CONCERN Printing Research, Inc.ADDRESS OF CONCERN 10954 Shady TrailDallas, Texas 75220

I hereby declare that the above-identified small business concern qualifies as a small business concern as defined in 13 C.F.R. §121.3-18, and reproduced in 37 C.F.R. §1.9(d), for purposes of paying reduced fees under Section 41(a) and (b) of Title 35, United States Code, in that the number of employees of the concern, including those of its affiliates, does not exceed 500 persons. For purposes of this statement, (1) the number of employees of the business concern is the average over the previous fiscal year of the concern of the persons employed on a full-time, part-time or temporary basis during each of the pay periods of the fiscal year, and (2) concerns are affiliates of each other when, either directly or indirectly, one concern controls or has the power to control the other, or a third-party or parties controls or has the power to control both.

I hereby declare that rights under license, contract or law have been acquired by or conveyed to and remain with the small business concern identified above with regard to the invention entitled

"RETRACTABLE INKING/COATING APPARATUS HAVING  
FERRIS MOVEMENT BETWEEN PRINTING UNITS"

by inventors Ronald M. Rendleman, Howard W. DeMoore and  
John W. Bird

as described in

- ☒ the specification filed herewith.  
☐ the specification filed \_\_\_\_\_ under Serial  
No. \_\_\_\_\_  
☐ Patent No. \_\_\_\_\_, issued \_\_\_\_\_.

If the rights held by the above-identified small business concern are not exclusive, each individual, concern or organization having rights to the invention is listed below and no rights to the invention are held by any person, other than the inventor, who could not qualify as a small business concern under 37 C.F.R. §1.9(d) or by any concern which would not qualify as a small business concern under 37 C.F.R. §1.9(d) or a nonprofit organization under 37 C.F.R. §1.9(e).

- ☒ no such person, concern or organization exists  
☐ any such person, concern or organization is identified below, if applicable:

Full Name \_\_\_\_\_

Address \_\_\_\_\_

- ☐ individual ☐ small business concern  
☐ nonprofit organization

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the date on which status as a small business entity is no longer appropriate. (37 C.F.R. §1.28(b)).

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or

09315706-001401

imprisonment, or both, under Section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

TYPED NAME OF PERSON SIGNING Howard W. DeMoore

TITLE OF PERSON OTHER THAN OWNER President and Chairman of  
the Board

Date: 1 May 1975

Howard W. DeMoore  
Signature

00346796 054101

TOP SECRET

86012  
RONALD M. RENDELMAN  
HOWARD W. DEMOORE  
JOHN W. BIRD

08 435798







FIG. 1



09435798 054101

FIG. 4

[illegible]





U.S. DEPARTMENT OF COMMERCE  
United States Patent and Trademark Office

**THIS IS TO CERTIFY** that page (s) fig. 6 is  
missing from the U.S. Patent and Trademark Office microform  
records.

K. White  
Certifying Officer

5/6/96  
DATE

00315796-BE1101

(5006791)  
(PGP790)

REMOVED PAYMENT CODINGS  
ZAHLUNGSBELEG - PAYMENT - PAIEMENT

27/06/96

67

FINANZ

GENERATED CODING

DOSSIER NR: 96303136.4

NR: 96303136.4

2 963031364

MEWBURN ELLIS

001 DEM	600,00	FFEE11	230596!
002 DEM	1900,00	SFEE11	230596!
005 DEM	1750,00	DEST13DE	230596!
		DEST13FR	230596!
		DEST13GB	230596!
		DEST13IT	230596!
		DEST13SE	230596!
015 DEM	960,00	CLMS12	230596!
055 DEM	40,00 ( X 1 )	ASOC13	230596!

BELEG-NR : 00012035  
REFERENCE-NR:

CLUSTER:009



P B 5818 - Patentlaan 2  
2280 HV Rijswijk (ZH)  
☎ (070) 3 40 20 40  
TX 31651 epo nl  
FAX (070) 3 40 30 16

Europäisches  
Patentamt

Zweigstelle  
in Den Haag  
Recherchen-  
abteilung

European  
Patent Office

Branch at  
The Hague  
Search  
division

Office européen  
des brevets

Département a  
La Haye  
Division de la  
recherche

10

Gura, Henry Alan  
MEWBURN ELLIS  
York House  
23 Kingsway  
London WC2B 6HP  
GRANDE BRETAGNE

COPY

Datum/Date  
15.04.97

Zerichen/Ref /Réf HAG/FP5233994	Anmeldung Nr /Application No /Demande n° //Patent Nr /Patent No /Brevet n° 96303136.4
Anmelder/Applicant/Demandeur//Patentinhaber/Proprietor/Titulaire DeMoore, Howard W.	

## COMMUNICATION

The European Patent Office herewith transmits


- ☒ the European search report
- ☐ the declaration under Rule 45 EPC
- ☐ the partial European search report under Rule 45 EPC
- ☐ the supplementary European search report concerning the international application under Article 157(2) EPC relating to the above-mentioned European patent application. Copies of the documents cited in the search report are enclosed.

The following specifications given by the applicant have been approved by the Search Division :

- ☒ Abstract ☒ Title ☒ Figure
- ☐ The abstract was modified by the Search Division and the definitive text is attached to this communication.
- ☐ The following figure will be published with the abstract, since the Search Division considers that it better characterises the invention than the one indicated by the applicant.

Figure:

- ☒ Additional copy(copies) of the documents cited in the European search report.



## REFUND OF THE SEARCH FEE

If applicable under Article 10 Rules relating to fees, a separate communication from the Receiving Section on the refund of the search fee will be sent later.

EPO Form 1507 02.93				



003636 001104  
"P01150" 95454600

DOCUMENTS CONSIDERED TO BE RELEVANT			
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Int.Cl.6)
X Y	US 4 841 903 A (BIRD)  * abstract; claims; figure 1 * ---	1,15-17 4-6,8,9, 13	B41F31/30 B41F5/24 B41F23/08
X	US 5 107 790 A (SLIKER ET AL.) * abstract; claim 1; figures * * column 2, line 9 - line 22 * ---	1,18	
Y	US 5 335 596 A (DEMOORE ET AL.) * abstract; figures 1-4 * * column 7, line 32 - line 58 * ---	4,5,8,9	
Y	US 4 617 865 A (SWITALL) * abstract; figures 1-3 * * column 6, line 9 - line 42 * ---	6	
Y	US 4 825 804 A (DIRICO ET AL.) * abstract; figures 2,3 * * column 3, line 10 - line 21 * ---	13	
A	EP 0 647 524 A (DEMOORE) * abstract; figures 1,2,5 * * column 4, line 32 - line 40 * ---	15-22	TECHNICAL FIELDS SEARCHED (Int.Cl.6)
A	PAPIER + KUNSTSTOFF VERARBEITER, vol. 26, no. 6, 1 June 1991, page 129 XP000232825 "LACKIER-AGGREGAT FUER SPEEDMASTER-MASCHINEN" -----	1	B41F
The present search report has been drawn up for all claims			
Place of search THE HAGUE		Date of completion of the search 20 March 1997	Examiner Helpiö, T
<b>CATEGORY OF CITED DOCUMENTS</b> X : particularly relevant if taken alone Y : particularly relevant if combined with another document of the same category A : technological background O : non-written disclosure P : intermediate document  T : theory or principle underlying the invention E : earlier patent document, but published on, or after the filing date D : document cited in the application L : document cited for other reasons ----- & : member of the same patent family, corresponding document			

1

EPO FORM 1503 03/82 (P04C01)

# ANNEX TO THE EUROPEAN SEARCH REPORT ON EUROPEAN PATENT APPLICATION NO.

EP 96 30 3136

This annex lists the patent family members relating to the patent documents cited in the above-mentioned European search report. The members are as contained in the European Patent Office EDP file on  
The European Patent Office is in no way liable for these particulars which are merely given for the purpose of information.

20-03-1997

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 4841903 A	27-06-89	US 4939992 A	10-07-90
US 5107790 A	28-04-92	NONE	
US 5335596 A	09-08-94	US 5176077 A	05-01-93
		US 5207159 A	04-05-93
		AT 148038 T	15-02-97
		AU 646197 B	10-02-94
		CA 2094694 A	07-11-93
		CN 1079689 A,B	22-12-93
		CZ 9300826 A	19-01-94
		DE 69307599 D	06-03-97
		EP 0574124 A	15-12-93
		JP 7178361 A	18-07-95
		KR 9612753 B	24-09-96
US 4617865 A	21-10-86	NONE	
US 4825804 A	02-05-89	JP 1045638 A	20-02-89
EP 647524 A	12-04-95	AU 675549 B	06-02-97
		AU 6895394 A	04-05-95
		BR 9403940 A	13-06-95
		CA 2129321 A	07-04-95
		CN 1109004 A	27-09-95
		CZ 9402450 A	14-06-95
		FI 944278 A	07-04-95
		JP 7164617 A	27-06-95
		NO 943706 A	07-04-95

EPO FORM P0439

For more details about this annex : see Official Journal of the European Patent Office, No. 12/82



EPA/EPO/OEB  
D-80298 München  
(089) 2399-0  
TX 523 656 epmu d  
FAX (089) 2399-4465

Europäisches  
Patentamt

European  
Patent Office

Office européen  
des brevets

Generaldirektion 2

Directorate General 2

Direction Générale 2

Gura, Henry Alan  
MEWBURN ELLIS  
York House  
23 Kingsway  
London WC2B 6HP  
GRANDE BRETAGNE

Telephone Numbers:

Primary Examiner (substantive examination) (089) 2399-2793

Formalities Officer / Assistant (Formalities and other matters) (089) 2399-2606



Application No 96 303 136.4-2304	Ref. HAG/FP5233994	Date 06.10.98
Applicant DeMoore, Howard W.		

Communication pursuant to Article 96(2) and Rule 51(2) EPC

The examination of the above-identified application has revealed that it does not meet the requirements of the European Patent Convention for the reasons enclosed herewith. If the deficiencies indicated are not rectified the application may be refused pursuant to Article 97(1) EPC.

You are invited to file your observations and insofar as the deficiencies are such as to be rectifiable, to correct the indicated deficiencies within a period

of 4 months

from the notification of this communication, this period being computed in accordance with Rules 78(3) and 83(2) and (4) EPC.

Amendments to the description, claims and drawings are to be filed where appropriate within the said period in three copies on separate sheets (Rule 36(1) EPC).

Failure to comply with this invitation in due time will result in the application being deemed to be withdrawn (Article 96(3) EPC).



SARTOR M  
Primary Examiner  
for the Examining Division

EXRE coded

Enclosure(s): 2 page/s reasons (Form 2906)

01.10.98 HJ

Registered Letter

EPO Form 2001 10 96CSX

AG22668, 30 09.1998



06. 10. 98

1

The examination is being carried out on the **following application documents:**

Text for the Contracting States:  
DE FR GB IT SE

**Description, pages:**

1-23 as originally filed

**Claims, No.:**

1-22 as originally filed

**Drawings, sheets:**

1/5-5/5 as originally filed

- 1.1 Claim 1 in its present form can be read over US-A-5 107 790 (see col. 3, lines 41-42, col. 5, lines 35-47, Fig.1) lacking therefore novelty (Art. 54 (1) (2) EPC). It is clear from the description on pages 2 and 3 that the following features, not comprised in claim 1 in its present form, are essential to the performance of the invention:

(1) "...the carriage assembly comprising a support arm having a first end portion constructed for pivotal attachment to the printing unit and a second end portion pivotally coupled to the applicator head, the applicator head being movable on the support arm between an operative position laterally adjacent to the plate and blanket cylinders and an elevated, retracted position in which the applicator head is elevated with respect to said plate and blanket cylinders..",

(2) "...a doctor blade assembly having a reservoir for receiving ink or liquid coating material.." and

(3) "...an applicator roller coupled to the doctor blade assembly in fluid

Datum  
Date  
Date

06. 10. 98

Blatt  
Sheet  
Feuille

2

Anmelde-Nr.:  
Application No.:  
Demande n° 96 303 136.4

communication with the reservoir, the applicator roller being engageable with a printing plate on the plate cylinder or with a blanket on the blanket cylinder when the applicator head is in the operative position."

Since independent claim 1 does not contain these features it does not meet the requirement following from Article 84 taken in combination with Rules 29(1) and (3) EPC that any independent claim must contain all the technical features essential to the invention.

In order to overcome the abovementioned objections a new claim 1 should therefore be filed, said claim containing the abovementioned features (1)-(3).

09315795 051101

- 1.2 The same objections raised on point 1.1 apply also to the subject-matter of independent claim 15.
3. To meet the requirements of Rule 27(1)(b) EPC, the document US-A-5 107 790 should be identified in the description and the relevant background art disclosed therein should be briefly discussed.



Volume of Paper: 4 pages  
 Number: 733-17-3  
 Date: 10/10/1963  
 File: 100-443888-100

Tel 0171 240 4405  
Fax 0171 240 9339  
Fax 0171 240 0652 (G4)  
DX 149 Chancery Lane  
Telex 22762 Patent G

Partners	Assisted by
1. A. G. G.	2. A. G. G.
3. A. G. G.	4. A. G. G.
5. A. G. G.	6. A. G. G.
7. A. G. G.	8. A. G. G.
9. A. G. G.	10. A. G. G.
11. A. G. G.	12. A. G. G.
13. A. G. G.	14. A. G. G.
15. A. G. G.	16. A. G. G.
17. A. G. G.	18. A. G. G.
19. A. G. G.	20. A. G. G.
21. A. G. G.	22. A. G. G.
23. A. G. G.	24. A. G. G.
25. A. G. G.	26. A. G. G.
27. A. G. G.	28. A. G. G.
29. A. G. G.	30. A. G. G.
31. A. G. G.	32. A. G. G.
33. A. G. G.	34. A. G. G.
35. A. G. G.	36. A. G. G.
37. A. G. G.	38. A. G. G.
39. A. G. G.	40. A. G. G.
41. A. G. G.	42. A. G. G.
43. A. G. G.	44. A. G. G.
45. A. G. G.	46. A. G. G.
47. A. G. G.	48. A. G. G.
49. A. G. G.	50. A. G. G.
51. A. G. G.	52. A. G. G.
53. A. G. G.	54. A. G. G.
55. A. G. G.	56. A. G. G.
57. A. G. G.	58. A. G. G.
59. A. G. G.	60. A. G. G.
61. A. G. G.	62. A. G. G.
63. A. G. G.	64. A. G. G.
65. A. G. G.	66. A. G. G.
67. A. G. G.	68. A. G. G.
69. A. G. G.	70. A. G. G.
71. A. G. G.	72. A. G. G.
73. A. G. G.	74. A. G. G.
75. A. G. G.	76. A. G. G.
77. A. G. G.	78. A. G. G.
79. A. G. G.	80. A. G. G.
81. A. G. G.	82. A. G. G.
83. A. G. G.	84. A. G. G.
85. A. G. G.	86. A. G. G.
87. A. G. G.	88. A. G. G.
89. A. G. G.	90. A. G. G.
91. A. G. G.	92. A. G. G.
93. A. G. G.	94. A. G. G.
95. A. G. G.	96. A. G. G.
97. A. G. G.	98. A. G. G.
99. A. G. G.	100. A. G. G.

8 February 1999

**European Patent Application No. 96303136.4-2304**  
**Howard W DeMoore**  
**Our Ref: HAG/FP5233994**

We regret we are not yet able to file a response to the outstanding official letter of 6 October 1998.

We would therefore request a two-month extension of time for this purpose.

Yours faithfully



H A Gura  
AUTHORISED REPRESENTATIVE

HAG/KA

Offices also at E  
Manchester Ne



EPA/EPO/OEB  
D-80298 München  
089/2399-0  
TX 523 656 epmu d  
FAX 089/2399-4465

Europäisches  
Patentamt

European  
Patent Office

Office européen  
des brevets

Generaldirektion 2

Directorate General 2

Direction Générale 2

**COPY**

Gura, Henry Alan  
MEWBURN ELLIS  
York House  
23 Kingsway  
London WC2B 6HP  
GRANDE BRETAGNE

Datum/Date

19.02.99

Zeichen/Ref./Réf. HAG/FP5233994	Anmeldung Nr./Application No./Demande n°/Patent Nr./Patent No./Brevet n° 96303136.4-2304/
Anmelder/Applicant/Demandeur/Patentinhaber/Proprietor/Titulaire DeMoore, Howard W.	

**EXTENSION OF TIME LIMIT PURSUANT TO RULE 84 EPC**

**Examination procedure**

With reference to your request dated ....., the time limit for replying to the communication dated 06.10.98 has been extended

by ..... months

to a total of ..... months,

from the date of notification of the above-mentioned communication.

[ ] Please note: To the extent that your request exceeded the above extension, your request has been refused.

**Note:**

The granting of extensions to time limits is governed by the implementing Regulations to the EPC and the Guidelines for Examination in the EPO, part E-VIII, 1.6.

If no reply to the communication is received in due time, the European patent application will be deemed to be withdrawn (Article 96(3) EPC).

For the Examining Division:

Tel. No.: (+49-89) 2399-8734

M. S. H. H.

EPO Form 2944A 04.97				7053035 16/02/99	

MEWBURN ELLIS  
INTELLECTUAL PROPERTY  
PATENTS · TRADEMARKS · DESIGNS

European Patent Office  
D-80298 Munich  
GERMANY

Chartered Patent Agents  
European Patent Attorneys  
Registered Trade Mark Agents  
European Trade Mark Attorneys

York House  
23 Kingsway  
London WC2B 6HP

Tel: 0171 240 4405  
Fax: 0171 240 9339  
Fax: 0171 240 0652 (G4)  
DX 149 Chancery Lane

Partners	Assisted by
H.A. Gals	R.E. Boley
D.C. Harrison	A.L. Brevster
J.M. Arnold	S.J. Carter
H.C.E. Page	J.L. Christensen
M.P. Ford	R. Collins
T.P. Calderbank	J.E. Cross
S.J. Linn	M.C. Foster
G.P. Storer	M.P. Freeman
C.J. O'Brien	R.S. Grimshaw
S.M. Walton	R.A. Hayward
N.J. MacFarlay	S.M. Palmer
F.J. Middle	J.M. Lyons
S.J. Hill	N.M. Medley
A.H. Braddon	K.M. Nicholson
	N.J. Sanderson
	A. Stuart
	D.A. Taylor
	N.L. Walker

16 April 1999

**BY FACSIMILE**

Dear Sirs

European Patent Application No. 96303136.4-2304  
Howard W DeMoore  
Our Ref: HAG/FP5233994

We are writing in reply to the official letter of 6 October 1998 and file herewith replacement copies of new pages 2, 3, 3a, 3b, 4 and 24-33 in triplicate for pages 2-4 and 24-33.

Claim 1 has been amended to distinguish it further from US 5,107,790 and, having regard to the Examiner's comments, to include a reference to the supply system for the ink or coating to be applied. However, we cannot agree with the Examiner that the disclosure in the specification requires that the claims should refer to those additional features set out in his comments. In particular, we dispute that the description on original pages 2 and 3 supports his contention.

In any case, it is necessary to look at the disclosure as a whole and it is clear that the claim as now amended has ample support in the application as filed. Specifically, the reference now in claim 1 to the ink or coating supply is sufficient for compliance with the requirements for support. It is not justifiable to require the applicant to limit his claim by including arbitrary elements of a preferred embodiment.

With regard to claim 15, it should be noted that this is not an independent claim as it refers to the inking/coating apparatus of the preceding claims. It thus imports all the features of claim 1 and requires no further particularisation.

The Examiner will note that we have taken the opportunity to make a number of formal changes in the claims, including the addition of multiple dependencies. There are also a few minor clerical errors to be corrected in the description, which the Examiner may find more convenient to undertake himself, namely:

contd/ ...

Offices also at Bristol Cambridge  
Manchester Newcastle

MEWBURN FLLIS

page 8,	line 21	correct "areas"
page 12.	line 2	delete "used"
	line 14	replace "86" with "58"

We believe the present amendments deal fully with the objections raised and thus place the application in order for allowance. As a formal matter, however we ask that if the intention should be formed to refuse the application we be given the opportunity for a hearing before any formal notice of rejection is issued.

Yours faithfully



H A Gura  
AUTHORISED REPRESENTATIVE

Encs

HAG/KA

[illegible]

18.04.92 S

line coating is performed, the last printing unit cannot be used to apply ink to the sheets, and can only be used for the coating operation. Thus, while coating with these types of in-line coating apparatus, the press loses the capability of printing its full range of colors since the last printing unit is converted to a coating unit.

It will be appreciated that the time required to reconfigure a press for coating or non-coating is non-productive and costly. Accordingly, there is a need for an in-line coating apparatus that minimizes the time to clean-up from one printing run and set-up and run the next job. Where consecutive jobs require the same type of coating, particularly blanket coating, it may not be necessary to clean-up the coater between jobs. However, the coating material cannot be allowed to dry on the rollers. Therefore, especially when switching from blanket to spot coating or vice versa, or if there is a delay between jobs, it is necessary to wash-up the coater after each job is completed.

In addition, coater wash-up is necessary when switching between different coating compositions, such as aqueous and ultra violet (UV) curable coatings. Such coating materials are not interchangeable, and consequently, the coater must be washed between applications of different coating media.

00315796 001104  
TOTAL 0025760

US 5,107,790 describes a two headed coater in which a spot coater assembly is disposed on one side of a plate cylinder and blanket cylinder pair and a blanket coating assembly is disposed on the other side of the cylinder pair. Each of the coating assemblies is slidable longitudinally away from the cylinder pair, in opposite directions, and the blanket coating assembly is also slidably displaceable along an inclined ramp, further away from the cylinder pair, these displacements being arranged to give access to each coating assembly. Such an arrangement requires a great deal of space and its usefulness is thus limited.

According to the present invention an inking/coating apparatus is provided for use in a printing press of the type having a printing unit on which a plate cylinder, a blanket cylinder and an impression cylinder are mounted for rotation, the apparatus comprising an applicator head for applying ink or coating materials to a plate mounted on the plate cylinder or to a blanket mounted on the blanket cylinder when the inking/coating apparatus is in the operative position relative to the plate and blanket cylinders, an applicator roller mounted in an applicator head being coupled with an ink or coating supply apparatus which provides a film of ink or coating on the applicator roll that can be transferred to said plate or blanket by movement of the applicator head being operative position, the applicator head to be pivotally mounted on a carriage assembly for movement to the operative position in

0915796-05101

## 3a

which the applicator head is disposed laterally adjacent to the plate and blanket cylinders, and for movement to a retracted position in which the applicator head is elevated with respect to the plate and blanket cylinders.

5           The carriage assembly may comprise a support arm which is preferably mounted on the printing press to be pivotally coupled between the inking/coating head and a printing unit tower of the press. The inking/coating unit can then be arranged to make a pivotal, Ferris wheel movement between the operative position and a retracted, overhead idle position. This cantilevered pivotal mounting arrangement can facilitate the use of the inking/coating head between two printing units as well as on the last printing unit of the press.

10  
15           In a preferred embodiment, the applicator head includes vertically spaced pairs of cradle members with one cradle pair being adapted for supporting a metal or ceramic coating roller in alignment with a blanket cylinder, and the other cradle pair supporting a resilient anilox coating roller in alignment with the plate cylinder, respectively, when the carriage assembly is in the operative position. Because of the cantilevered, pivotal support provided by the support arm, the applicator head can be lifted and lowered through an arc, similar to Ferris wheel movement, in the limited space between adjacent printing units. When fully retracted, the applicator head and carriage assembly are lifted to an elevated, retracted overhead position, preferably an overhead position overlying the printing unit

0934E796 DE 1101

30

tower, thus providing complete access to the interstation space and the printing unit cylinders without causing the printing unit to lose its printing capability. The

[illegible]



inking/coating applicator roller of the applicator head can be inspected, cleaned or replaced and the doctor blade assembly can be washed-up automatically while the inking/coating apparatus is in the retracted position.

5                   When the inking/coating apparatus is used in combination with a flexographic printing plate and aqueous ink or aqueous coating, it is preferred to arrange that the water component of the aqueous ink or coating on the freshly printed sheet is evaporated by a high velocity, hot air interstation dryer and a high  
10 volume heat and moisture extractor assembly so that the freshly printed ink or coating is completely dry before the sheet is printed on the next printing unit. This quick drying flexographic printing/coating arrangement permits a base coat of ink, for example opaque white or metallic ink  
15 (gold, silver or other metallics) to be applied in the first printing unit, and then overprinted by a lithographic process on the next printing unit.

Exemplary embodiments of the present invention are illustrated in the drawing figures wherein:

20                   FIGURE 1 is a schematic side elevational view of a sheet-fed, rotary offset printing press having inking/coating apparatus embodying the present invention;

                  FIGURE 2 is a perspective view of the printing press of FIGURE 1 in which a dual head inking/coating  
25 apparatus is in the operative coating position and a single head coater is in a retracted, overhead position;

00745796-551104  
TOP SECRET

## CLAIMS

1. Inking/coating apparatus (10) for use in a printing press (12) of the type having a printing unit (22,24,26,28) on which a plate cylinder (32), a blanket cylinder (34) and an impression cylinder (36) are mounted for rotation, wherein the inking/coating apparatus comprises:

an applicator head (60) for applying ink or coating materials to a plate (P) mounted on the plate cylinder or to a blanket (B) mounted on the blanket cylinder, when the inking/coating apparatus is in the operative position relative to the plate and blanket cylinders,

an applicator roller (66) mounted in applicator head (60) being coupled with an ink or coating supply apparatus (68) which provides a film of ink or coating on the applicator roller that can be transferred to said plate or blanket by movement of the applicator head to the operative position; and is characterised by

the applicator head (60) being pivotally mounted on a carriage assembly (58) for movement to the operative position in which the applicator head is disposed laterally adjacent to the plate and blanket cylinders and for movement to a retracted position in which the applicator head is elevated with respect to the plate and blanket cylinders.

2. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) comprises:

5 a support arm (88,90) having a first end portion (88A) constructed for pivotal attachment to the printing unit and having a second end portion (88B) pivotally coupled to the applicator head (60), the applicator head being movable on the support arm to the operative position.

3. Inking/coating apparatus (10) as set forth in claim 1 or claim 2, wherein a counterweight (100,102) is coupled to the carriage assembly.

10 4. Inking/coating apparatus (10) as set forth in any one of claims 1 to 3, wherein the applicator head (60) comprises:

15 a doctor blade assembly (68) having a reservoir (70) for receiving ink or liquid coating material; and, the applicator roller (66) being coupled to the doctor blade assembly in fluid communication with the reservoir.

5. Inking/coating apparatus (10) as set forth in claim 4, wherein the applicator roller (66) is an anilox roller having a resilient transfer surface.

00345000 DE 44 101

-26-

6. Inking/coating apparatus (10) as set forth  
in any one of claims 1 to 5, wherein:

a power actuator (104, 106) is movably  
coupled to the applicator head (60), the power actuator  
5 having a power transfer arm (104A, 106A) which is extend-  
able and retractable; and,

movement converting apparatus (108) is  
coupled to the power transfer arm for converting extension  
or retraction movement of the power transfer arm into  
10 pivotal movement of the applicator head (60) relative to  
the carriage assembly.

7. Inking/coating apparatus (10) as set forth  
in claim 6, wherein the movement converting apparatus (108)  
comprises:

15 a bell crank plate (111) having a first end  
portion coupled to the power transfer arm and having a  
second end portion for engaging a stop member;

a stop member (119) secured to the applica-  
tor head (60); and,

20 a clevis plate (115) secured to the carriage  
assembly (58) and pivotally coupled to the bell crank  
plate.

8. Inking/coating apparatus (10) as set forth  
in any one of claims 1 to 3, wherein the applicator head (60) comprises:

25

00315796 054101  
F0150 96/5120

first and second side frame members (74, 76)  
pivotally coupled to the carriage assembly (58);

a doctor blade assembly mounted on the first  
and second side frame members, the doctor blade assembly  
5 including a reservoir (70) for receiving ink or liquid  
coating material;

a cradle assembly (78, 80), (82, 84) mounted  
on the first and second side frame members, respectively;  
the applicator roller (66) being mounted for

10 rotation on the cradle assembly and coupled to the doctor  
blade assembly for rolling contact with ink or coating  
material in the reservoir; and

15

a drive motor (62) coupled to the applicator  
roller for rotating the applicator roller.

9. Inking/coating apparatus (10) as set forth  
20 in claim 8, wherein:

the cradle assembly (79, 80) has first and  
second sockets (79, 81) disposed on the first and second  
side frame members respectively; and,

the applicator roller (66) is mounted for  
25 rotation on the first and second sockets.

003413796 DE4401  
FOTRAD 06/25/2000

10. Inking/coating apparatus (10) as set forth  
in claim 8, wherein:

the cradle assembly (78, 80), (82, 84)  
includes first and second sockets (79, 81) disposed on the  
5 first and second side frame members, respectively, and  
third and fourth sockets disposed on the first and second  
side frame members, respectively; and,

the applicator roller (66) is selectively  
mountable for rotation on either the first and second  
10 sockets or on the third and fourth sockets for applying ink  
or coating material to either the plate or blanket when the  
applicator head is in the operative position.

11. Inking/coating apparatus (10) as set forth  
in any one of claims 1 to 7, wherein the applicator head (60) comprises:

15 a first cradle (78, 80) for supporting an  
applicator roller (66) for engagement with the plate when  
the inking/coating apparatus is in the operative position;  
and

20 a second cradle (82, 84) for supporting an  
applicator roller (66) for engagement with the blanket (B)  
when the inking/coating apparatus is in the operative  
position.

12. Inking/coating apparatus (10) as set forth  
25 in claim 1, wherein the carriage assembly comprises:

00345736 DE 4101  
TOTAL 962560

a support arm (88, 90) having a first end portion pivotally coupled to the printing unit (88A, 90A) and having a second end portion (88B, 90B);

5 a common pivot shaft (77) on which the support arm second end portion and the inking/coating apparatus are pivotally mounted; and,

male and female latch members (103, 105) coupled between the common pivot shaft and the printing unit, with one of the latch members being secured to the common pivot shaft and the other latch member being constructed for attachment onto the printing unit, the latch members being mateable in interlocking engagement when the applicator head (60) is in the operative position.

13. Inking/coating apparatus (10) as set forth in any one of the preceding claims, wherein the applicator head (60) and the printing unit comprise:

male and female latch coupling members (103, 105) mounted on the carriage assembly (58) and on the printing unit for releasably latching the carriage assembly in interlocking engagement with the printing unit when the applicator head is in the operative position.

14. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) comprises

an elongated shank portion (88B, 90B) and a hub portion (88A, 90A), the elongated shank portion being pivotally coupled to the applicator head (60) and the hub

00345796-054104

-30-

portion being constructed for pivotal attachment onto the printing unit.

15 15. A rotary offset printing press (12) having first and second printing units (22, 24) and the ink-  
ing/coating apparatus (10) of any one of the preceding claims movably coupled to the first printing unit (22) as set forth in claim 1,  
wherein:

10 a dryer (112) mounted on the first printing unit adjacent the impression cylinder (36) of the first printing unit for discharging heated air onto a freshly printed substrate while the freshly printed substrate is in contact with said impression cylinder.

15 16. A rotary offset printing press (12) as defined in claim 15, comprising:

an extractor (112E) is disposed adjacent the dryer for extracting hot air, moisture and volatiles from an exposure zone (Z) between the dryer and the freshly printed substrate.

20 17. A rotary offset printing press (12) as defined in claim 15 or claim 16, comprising

an intermediate transfer cylinder (40) is coupled in sheet transfer relation with the impression cylinder (36) of the first printing unit (22); and,

25 an interstation dryer (114) is disposed adjacent the intermediate transfer cylinder for discharging

00315796-051101  
TOTSO 96251500



heated air onto a freshly printed or coated substrate after it has been transferred from the impression cylinder of the first printing unit and while it is in contact with the intermediate transfer cylinder (40).

5 18. A method for rotary offset printing in a printing press (12) of the type including first and second rotary offset printing units (22, 24), and using aqueous or UV-curable printing ink or coating material in the operation of at least the first printing unit, characterized by  
10 the following steps performed at each printing unit in succession:

spot or overall coating a plate (P) with aqueous ink/aqueous coating material or UV-curable ink/UV-curable coating material;

15 spot and/or overall coating a blanket (B) with aqueous ink/aqueous coating material or UV-curable ink or UV-curable coating material;

transferring the printing ink or coating material from the printing plate (P) to the blanket (B);

20 transferring the inked or coated image from the blanket to a substrate (S) as the substrate is transferred through the nip between the impression cylinder (36) and the blanket (B); and,

drying the ink or coating material on the  
25 freshly printed substrate before the substrate is subsequently processed.

00115795-054101

-32-

19. A method for rotary offset printing as defined in claim 18, wherein the drying step comprises:

5       discharging high velocity, heated air onto the freshly printed/coated substrate (S) while the freshly printed/coated substrate is in contact with the impression cylinder (36) of the first printing unit (22).

20. A method for rotary offset printing as defined in claim 18 further comprising:

10       transferring the freshly printed substrate (S) from the first printing unit (22) to an intermediate transfer cylinder (40); and,

      drying the freshly printed substrate while it is in contact with the intermediate transfer cylinder.

15       21. A method for rotary offset printing as defined in claim 18 or claim 19, further comprising:

      extracting hot air, moisture and volatiles from an exposure zone (Z) above the freshly printed/coated substrate (S) while the freshly printed/coated substrate is  
20       in contact with the impression cylinder (36).

22. A method for rotary offset printing as defined in any one of claims 18 to 21, further comprising:

      applying a primer coating of an aqueous coating material or UV-curable coating material to a  
25       substrate (S) in the first printing unit (22); and,

00345746 034101  
TOTAL 0345746



**MEWBURN ELLIS**  
INTELLECTUAL PROPERTY  
PATENTS • TRADE MARKS • DESIGNS

Chartered Patent Agents  
European Patent Attorneys  
Registered Trade Mark Agents  
European Trade Mark Attorneys

York House  
23 Kingsway  
London WC2B 6HP

Tel 0171 240 4405  
Fax 0171 240 9339  
Fax 0171 240 0652 (G4)  
DX 149 Chancery Lane  
Telex 22762 Patent G

Partners  
H.A. Gura  
D.C. Hamson  
I.M. Armitage  
H.C.E. Paget  
M.F. Ford  
T.R. Calderbank  
S.J. Linn  
G.P. Stoner  
C.J. O'Brien  
S.M. Walton  
N.J. Mackley  
S.J. Kiddle  
S. Hill  
A.H. Brasnett  
Not CPA or EPA

Assisted by  
R.E. Body  
A.R. Brewster  
S.J. Carter  
J.L. Christensen  
J.E. Cripps  
R. Colaire  
M.G. Foster  
M.P. Freeman  
R.S. Grimshaw  
A.A. Hayano  
S.M. Kramer  
J.M. Lyons  
M.M.T. Medysky  
K.M. Nicholls  
M.J. Sanderson  
I.A. Stuart  
D.A. Taylor  
T.L. Wain

**FACSIMILE**

DATE: 16 April 1999

TO:

COMPANY: European Patent Office - Munich

OUR FAX NO: 0171 240 9339 and 0171 240 0652  
+ 44 171 240 9339 and + 44 171 240 0652 (G4)

OUR REF: HAG/FP5233994

Total number of sheets being transmitted including this cover page 18

If you do not receive all of the pages, please fax us as soon as possible or phone us on 0171 240 4405  
+ 44 171 240 4405

This communication is intended only for the use of the addressee and may contain information that is privileged and confidential. If you are not the intended recipient, you are hereby notified that the unauthorised dissemination of this communication may be prohibited by law. If you have received this communication in error, please notify Mewburn Ellis immediately by telephone, fax or telex. Thank you.

Offices also at Bristol Cambridge  
Manchester Newcastle

003396 061101  
F01T50 9644460

Offices also at  
Manchester N

page 8,	line 21	correct "areas"
page 12,	line 2	delete "used"
	line 14	replace "86" with "58"

We believe the present amendments deal fully with the objections raised and thus place the application in order for allowance. As a formal matter, however we ask that if the intention should be formed to refuse the application we be given the opportunity for a hearing before any formal notice of rejection is issued.

Yours faithfully



H A Gura  
AUTHORISED REPRESENTATIVE

Encs

HAG/KA

00345736 00404  
00345736 00404

22.3.93 SH  
22.3.93 SH

line coating is performed, the last printing unit cannot be used to apply ink to the sheets, and can only be used for the coating operation. Thus, while coating with these types of in-line coating apparatus, the press loses the capability of printing its full range of colors since the last printing unit is converted to a coating unit.

It will be appreciated that the time required to reconfigure a press for coating or non-coating is non-productive and costly. Accordingly, there is a need for an in-line coating apparatus that minimizes the time to clean-up from one printing run and set-up and run the next job. Where consecutive jobs require the same type of coating, particularly blanket coating, it may not be necessary to clean-up the coater between jobs. However, the coating material cannot be allowed to dry on the rollers. Therefore, especially when switching from blanket to spot coating or vice versa, or if there is a delay between jobs, it is necessary to wash-up the coater after each job is completed.

In addition, coater wash-up is necessary when switching between different coating compositions, such as aqueous and ultra violet (UV) curable coatings. Such coating materials are not interchangeable, and consequently, the coater must be washed between applications of different coating media.

US 5,107,790 describes a two headed coater in which a spot coater assembly is disposed on one side of a plate cylinder and blanket cylinder pair and a blanket coating assembly is disposed on the other side of the cylinder pair. Each of the coating assemblies is slidable longitudinally away from the cylinder pair, in opposite directions, and the blanket coating assembly is also slidably displaceable along an inclined ramp, further away from the cylinder pair, these displacements being arranged to give access to each coating assembly. Such an arrangement requires a great deal of space and its usefulness is thus limited.

According to the present invention an inking/coating apparatus is provided for use in a printing press of the type having a printing unit on which a plate cylinder, a blanket cylinder and an impression cylinder are mounted for rotation, the apparatus comprising an applicator head for applying ink or coating materials to a plate mounted on the plate cylinder or to a blanket mounted on the blanket cylinder when the inking/coating apparatus is in the operative position relative to the plate and blanket cylinders, an applicator roller mounted in an applicator head being coupled with an ink or coating supply apparatus which provides a film of ink or coating on the applicator roll that can be transferred to said plate or blanket by movement of the applicator head being operative position, the applicator head to be pivotally mounted on a carriage assembly for movement to the operative position in



which the applicator head is disposed laterally adjacent to the plate and blanket cylinders, and for movement to a retracted position in which the applicator head is elevated with respect to the plate and blanket cylinders.

5           The carriage assembly may comprise a support arm which is preferably mounted on the printing press to be pivotally coupled between the inking/coating head and a printing unit tower of the press. The inking/coating unit can then be arranged to make a pivotal, Ferris wheel movement between the operative position and a retracted, overhead idle position. This cantilevered pivotal mounting arrangement can facilitate the use of the inking/coating head between two printing units as well as on the last printing unit of the press.

10  
15           In a preferred embodiment, the applicator head includes vertically spaced pairs of cradle members with one cradle pair being adapted for supporting a metal or ceramic coating roller in alignment with a blanket cylinder, and the other cradle pair supporting a resilient anilox coating roller in alignment with the plate cylinder, respectively, when the carriage assembly is in the operative position. Because of the cantilevered, pivotal support provided by the support arm, the applicator head can be lifted and lowered through an arc, similar to Ferris wheel movement, in the limited space between adjacent printing units. When fully retracted, the applicator head and carriage assembly are lifted to an elevated, retracted overhead position, preferably an overhead position overlying the printing unit

14 1043

3b

tower, thus providing complete access to the interstation space and the printing unit cylinders without causing the printing unit to lose its printing capability. The

00345736 004404

inking/coating applicator roller of the applicator head can be inspected, cleaned or replaced and the doctor blade assembly can be washed-up automatically while the inking/coating apparatus is in the retracted position.

5                   When the inking/coating apparatus is used in combination with a flexographic printing plate and aqueous ink or aqueous coating, it is preferred to arrange that the water component of the aqueous ink or coating on the freshly printed sheet is evaporated by a high velocity, hot air interstation dryer and a high  
10 volume heat and moisture extractor assembly so that the freshly printed ink or coating is completely dry before the sheet is printed on the next printing unit. This quick drying flexographic printing/coating arrangement permits a base coat of ink, for example opaque white or metallic ink  
15 (gold, silver or other metallics) to be applied in the first printing unit, and then overprinted by a lithographic process on the next printing unit.

Exemplary embodiments of the present invention are illustrated in the drawing figures wherein:

20                   FIGURE 1 is a schematic side elevational view of a sheet-fed, rotary offset printing press having inking/coating apparatus embodying the present invention;

                  FIGURE 2 is a perspective view of the printing press of FIGURE 1 in which a dual head inking/coating  
25 apparatus is in the operative coating position and a single head coater is in a retracted, overhead position;

## CLAIMS

1. Inking/coating apparatus (10) for use in a printing press (12) of the type having a printing unit (22,24,26,28) on which a plate cylinder (32), a blanket cylinder (34) and an impression cylinder (36) are mounted for rotation, wherein the inking/coating apparatus comprises:

an applicator head (60) for applying ink or coating materials to a plate (P) mounted on the plate cylinder or to a blanket (B) mounted on the blanket cylinder, when the inking/coating apparatus is in the operative position relative to the plate and blanket cylinders,

an applicator roller (66) mounted in applicator head (60) being coupled with an ink or coating supply apparatus (68) which provides a film of ink or coating on the applicator roller that can be transferred to said plate or blanket by movement of the applicator head to the operative position; and is characterised by

the applicator head (60) being pivotally mounted on a carriage assembly (58) for movement to the operative position in which the applicator head is disposed laterally adjacent to the plate and blanket cylinders and for movement to a retracted position in which the applicator head is elevated with respect to the plate and blanket cylinders.

2. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) comprises:

a support arm (88,90) having a first end portion (88A) constructed for pivotal attachment to the printing unit and having a second end portion (88B) pivotally coupled to the applicator head (60), the applicator head  
5 being movable on the support arm to the operative position.

3. Inking/coating apparatus (10) as set forth in claim 1 or claim 2, wherein a counterweight (100,102) is coupled to the carriage assembly.

4. Inking/coating apparatus (10) as set forth in any  
10 one of claims 1 to 3, wherein the applicator head (60) comprises:

a doctor blade assembly (68) having a reservoir (70) for receiving ink or liquid coating material; and,  
the applicator roller (66) being coupled to the  
15 doctor blade assembly in fluid communication with the reservoir.

5. Inking/coating apparatus (10) as set forth in claim 4, wherein the applicator roller (66) is an anilox roller having a resilient transfer surface.

6. Inking/coating apparatus (10) as set forth in any one of claims 1 to 5, wherein:

5 a power actuator (104, 106) is movably coupled to the applicator head (60), the power actuator having a power transfer arm (104A, 106A) which is extend-  
able and retractable; and,

10 movement converting apparatus (108) is coupled to the power transfer arm for converting extension or retraction movement of the power transfer arm into pivotal movement of the applicator head (60) relative to the carriage assembly.

7. Inking/coating apparatus (10) as set forth in claim 6, wherein the movement converting apparatus (108) comprises:

15 a bell crank plate (111) having a first end portion coupled to the power transfer arm and having a second end portion for engaging a stop member;

a stop member (119) secured to the applicator head (60); and,

20 a clevis plate (115) secured to the carriage assembly (58) and pivotally coupled to the bell crank plate.

8. Inking/coating apparatus (10) as set forth in any one of claims 1 to 3, wherein the applicator head (60) comprises:

first and second side frame members (74, 76) pivotally coupled to the carriage assembly (58);

a doctor blade assembly mounted on the first and second side frame members, the doctor blade assembly including a reservoir (70) for receiving ink or liquid coating material;

a cradle assembly (78, 80), (82, 84) mounted on the first and second side frame members, respectively; the applicator roller (66) being mounted for

rotation on the cradle assembly and coupled to the doctor blade assembly for rolling contact with ink or coating material in the reservoir; and

a drive motor (62) coupled to the applicator roller for rotating the applicator roller.

9. Inking/coating apparatus (10) as set forth in claim 8, wherein:

the cradle assembly (79, 80) has first and second sockets (79, 81) disposed on the first and second side frame members respectively; and,

the applicator roller (66) is mounted for rotation on the first and second sockets.

10. Inking/coating apparatus (10) as set forth  
in claim 8, wherein:

the cradle assembly (78, 80), (82, 84)  
includes first and second sockets (79, 81) disposed on the  
5 first and second side frame members, respectively, and  
third and fourth sockets disposed on the first and second  
side frame members, respectively; and,

the applicator roller (66) is selectively  
mountable for rotation on either the first and second  
10 sockets or on the third and fourth sockets for applying ink  
or coating material to either the plate or blanket when the  
applicator head is in the operative position.

11. Inking/coating apparatus (10) as set forth  
in any one of claims 1 to 7, wherein the applicator head (60) comprises:

15 a first cradle (78, 80) for supporting an  
applicator roller (66) for engagement with the plate when  
the inking/coating apparatus is in the operative position;  
and

20 a second cradle (82, 84) for supporting an  
applicator roller (66) for engagement with the blanket (B)  
when the inking/coating apparatus is in the operative  
position.

12. Inking/coating apparatus (10) as set forth  
25 in claim 1, wherein the carriage assembly comprises:

0045796-05140



a support arm (88, 90) having a first end portion pivotally coupled to the printing unit (88A, 90A) and having a second end portion (88B, 90B);

5 a common pivot shaft (77) on which the support arm second end portion and the inking/coating apparatus are pivotally mounted; and,

10 male and female latch members (103, 105) coupled between the common pivot shaft and the printing unit, with one of the latch members being secured to the common pivot shaft and the other latch member being constructed for attachment onto the printing unit, the latch members being mateable in interlocking engagement when the applicator head (60) is in the operative position.

15 13. Inking/coating apparatus (10) as set forth in any one of the preceding claims, wherein the applicator head (60) and the printing unit comprise :

20 male and female latch coupling members (103, 105) mounted on the carriage assembly (58) and on the printing unit for releasably latching the carriage assembly in interlocking engagement with the printing unit when the applicator head is in the operative position.

14. Inking/coating apparatus (10) as set forth in claim 1, wherein the carriage assembly (58) comprises

25 an elongated shank portion (88B, 90B) and a hub portion (88A, 90A), the elongated shank portion being pivotally coupled to the applicator head (60) and the hub

portion being constructed for pivotal attachment onto the printing unit.

15. A rotary offset printing press (12) having first and second printing units (22, 24) and the ink-  
5 ing/coating apparatus (10) of any one of the preceding claims movably coupled to the first printing unit (22) as set forth in claim 1, wherein:

10 a dryer (112) mounted on the first printing unit adjacent the impression cylinder (36) of the first printing unit for discharging heated air onto a freshly printed substrate while the freshly printed substrate is in contact with said impression cylinder.

16. A rotary offset printing press (12) as defined in claim 15, comprising:

15 an extractor (112E) is disposed adjacent the dryer for extracting hot air, moisture and volatiles from an exposure zone (Z) between the dryer and the freshly printed substrate.

17. A rotary offset printing press (12) as  
20 defined in claim 15 or claim 16, comprising

an intermediate transfer cylinder (40) is coupled in sheet transfer relation with the impression cylinder (36) of the first printing unit (22); and,

25 an interstation dryer (114) is disposed adjacent the intermediate transfer cylinder for discharging

0033706 054404  
F07T50 0425500

heated air onto a freshly printed or coated substrate after it has been transferred from the impression cylinder of the first printing unit and while it is in contact with the intermediate transfer cylinder (40).

5 18. A method for rotary offset printing in a printing press (12) of the type including first and second rotary offset printing units (22, 24), and using aqueous or UV-curable printing ink or coating material in the operation of at least the first printing unit, characterized by  
10 the following steps performed at each printing unit in succession:

spot or overall coating a plate (P) with aqueous ink/aqueous coating material or UV-curable ink/UV-curable coating material;

15 spot and/or overall coating a blanket (B) with aqueous ink/aqueous coating material or UV-curable ink or UV-curable coating material;

transferring the printing ink or coating material from the printing plate (P) to the blanket (B);

20 transferring the inked or coated image from the blanket to a substrate (S) as the substrate is transferred through the nip between the impression cylinder (36) and the blanket (B); and,

25 drying the ink or coating material on the freshly printed substrate before the substrate is subsequently processed.

00315795.05:104

19. A method for rotary offset printing as defined in claim 18, wherein the drying step comprises:

5       discharging high velocity, heated air onto the freshly printed/coated substrate (S) while the freshly printed/coated substrate is in contact with the impression cylinder (36) of the first printing unit (22).

20. A method for rotary offset printing as defined in claim 18 further comprising:

10       transferring the freshly printed substrate (S) from the first printing unit (22) to an intermediate transfer cylinder (40); and,

      drying the freshly printed substrate while it is in contact with the intermediate transfer cylinder.

15       21. A method for rotary offset printing as defined in claim 18 or claim 19, further comprising:

      extracting hot air, moisture and volatiles from an exposure zone (Z) above the freshly printed/coated substrate (S) while the freshly printed/coated substrate is  
20       in contact with the impression cylinder (36).

22. A method for rotary offset printing as defined in any one of claims 18 to 21, further comprising:

      applying a primer coating of an aqueous coating material or UV-curable coating material to a  
25       substrate (S) in the first printing unit (22); and,

drying the primer coating on the substrate before the substrate is processed in the second printing unit.

00315796 001101



# Antrag auf Erteilung eines europäischen Patents / Request for grant of a European patent / Requête en délivrance d'un brevet européen

Bestätigung einer bereits durch Telex oder Teletex eingereichten Anmeldung / Confirmation d'une demande déjà déposée par télex ou par telex / Confirmation d'une demande déjà déposée par télex ou par telex  
Wenn ja, Datum der Übermittlung der Telex und Name der Einrichtung, die die Telex übermittelte / If yes, date and name of the authority with which the documents were filed / Si oui, date d'envoi de la telex et nom de l'autorité de dépôt

☐ Ja / Yes / Oui

Datum / Date Behörde / Authority / Autorité

Nur für amtlichen Gebrauch / For official use only / Cadre réservé à l'administration

Anmeldenummer / Application No. / N. de la demande

MKEY

1

Tag des Eingangs / Regel 24(2) / Date of receipt (Rule 24(2)) / Date de réception (règle 24(2))

DREC

2

14.05.1996

Tag des Eingangs beim EPA (Regel 24(4)) / Date of receipt at EPO (Rule 24(4)) / Date de réception à l'OEB (règle 24(4))

RENA

3

14.05.96

Anmeldetag / Date of filing / Date de dépôt

4

Tabulatoren-Positionen / Tabulation marks / Arrêts de tabulation

Es wird die Erteilung eines europäischen Patents und gemäß Artikel 94 die Prüfung der Anmeldung beantragt / Grant of a European patent, and examination of the application under Article 94, are hereby requested / Il est demandé la délivrance d'un brevet européen et, conformément à l'article 94, l'examen de la demande

EXAM 4

5

Prüfungsantrag in einer zugelassenen Nichtamtssprache (siehe Merkblatt II, 5) / Request for examination in an admissible non-EPO language (see Notes II, 5) / Requête en examen dans une langue non officielle autorisée (voir notice II, 5)

Zeichen des Anmelders oder Vertreters (max. 15 Positionen) / Applicant's or representative's reference (maximum 15 spaces) / Référence du demandeur ou du mandataire (max. 15 caractères ou espaces)

AREF

6

HAG/FP5233994

ANMELDER / APPLICANT / DEMANDEUR  
Name / Nom

7

HOWARD WARREN DEMOORE

Anschrift / Address / Adresse

8

10954 Shady Trail  
Dallas  
Texas 75220  
USA

APPR 01 #

# DEST #

Zustellschrift / Address for correspondence / Adresse pour la correspondance

9

PADR

Staat des Wohnsitzes oder Sitzes / State of residence or of principal place of business / Etat du domicile ou du siège

10

Staatsangehörigkeit / Nationality / Nationalité

11

USA

Telefon / Telephone / Téléphone

12

Telex / Telex

Telefax / Fax / Téléfax

13

Weitere(r) Anmelder auf Zusatzblatt / Additional applicant(s) on additional sheet / Autre(s) demandeur(s) sur feuille additionnelle

14

VERTRETER / REPRESENTATIVE / MANDATAIRE:  
Name / Nom

15

H A GURA and Others

(Nur einen Vertreter angeben, der in das europäische Patentregister eingetragen und an den zugestellt wird / Name only one representative, who is to be listed in the Register of European Patents and to whom notification is to be made / N. indiquer qu'un seul mandataire, qui sera inscrit au Registre européen des brevets et auquel signification sera faite)

PREP 01

03/31/22#

#1#

Geschäftsanschrift / Address of place of business / Adresse professionnelle

16

MEWBURN ELLIS  
York House  
23 Kingsway  
LONDON WC2B 6HP

Telefon / Telephone / Téléphone

17

0171 240 4405

Telex / Télex

Telefax / Fax / Téléfax

18

22762 Patent G

0171 240 9339

Weitere(r) Vertreter auf Zusatzblatt / Additional representative(s) on additional sheet / Autre(s) mandataire(s) sur feuille additionnelle

19

X